


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by Nygren in 1977.



Description of corner evidence found:


Found 5/8" iron rod with 1 1/2 " plastic cap marked "Nygren RS 1035" from which a:
18" White Fir BT (record Douglas Fir), scribes visible, bears S22 1/2°W, 8.3 feet.
26" Cedar BT, scribes visible, bears N27°W, 27.7 feet (record N22°W).

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point I set a 2" iron pipe with a 2 1/2" brass cap marked "T31S, R2W, W.M., NE 1/16, S34, RLS 430, 1980" and reset Nygren's 5/8" iron rod alongside.



BA Shaner



I hereby certify the above corner monument was re-established as herein described on July 24, 1980.

Office of..... Surveyor..... County of..... Douglas.....

State of..... OREGON....., I hereby certify that the within instrument was filed in this office for record on the..... 14..... day of..... August....., 19..... 80.....

..... Francis L. Ingram..... by..... *Virginia A. Haugen*.....
(COUNTY OFFICIAL) (DEPUTY)

50/229
32