


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by Nygren in 1977.



Description of corner evidence found:

Found 5/8" iron rod with 1 1/4" plastic cap marked "Nygren RS1035" from which a:
11" Hemlock BT (record red fir), scribes visible, bears S28°E, 10.0 feet
(Record S34°E).
8" Douglas Fir BT, scribes visible, bears S35°W, 13.9 feet.

Description of monument and accessories I established to perpetuate the original location of this corner:

On corner point I set a 2" iron pipe with a 2 1/2" brass cap marked "T31S, R2W, W.M., NW 1/16, S34, RLS 430, 1980".
I reset Nygren's 5/8" iron rod alongside brass cap.



BA Shaner



I hereby certify the above corner monument was re-established as herein described on July 21, 1980.

Office of..... Surveyor..... County of..... Douglas.....
Oregon..... State of..... I hereby certify that the within instrument was filed in this office
for record on the..... 14 day of..... August....., 1980

Francis L. Ingram..... by *Virginia A. Suggs*
(COUNTY OFFICIAL)..... (DEPUTY)

58/2290