

M 92-48 M 92-49

PEEL BAKER LAND SURVEYING, INC.

1262 Lawrence Street, Suite 4
EUGENE, OREGON 97401
Telephone: (503) 343-7243

Home Telephones:
Don Peel, PLS 344-1828
Dan Baker 484-2734

July 28, 1982

FILED
RECEIVED *BS*

JUL 30 1982

Douglas County Surveyor
Room 205--Justice Building
Roseburg, OR 97470

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Attention: Mr. Larry E. Monrean


Dear Mr. Monrean:

Enclosed find two survey plats to be filed for record.

1. Section 26, T21S, R6W, W.M. I have made your suggested corrections.
2. Section 33, T19S, R10W, W.M., with a \$10.00 check to cover the filing fee.

Concerning the 1/2" x 60" rebar you mentioned, I can see where one should have a short explanation of our rebar procedure. The rebar is not set monument-style but is more on the order of fence posts like the U.S. Forest Service uses to delineate property lines. Each rebar is left protruding 2-1/2 to 3 feet above the ground. Attached to the upper portion of the rebar is a yellow 4" x 8" sign marked "Property Line, International Paper Co., Gardiner, Oregon." Each sign is stamped with the traverse point number, the distance (to the nearest foot) and bearing (north, south, east or west) to the nearest corner, what corner that is (i.e., the nearest corner), and my Professional Land Surveyor's registration number. Each rebar is set ± 0.2 feet from true line.

Sincerely yours,



Donald L. Peel, PLS

Enclosures