

M 96-26

FILED  
RECEIVED *BS*

MAR 29 1984

OREGON CORNER RESTORATION FORM


Section 35 Township 20S Range 9W

County Douglas Date 2-15-84

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

Corner Designation

S.E. Corner  
Section 35



- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. Thomas A. Tillman and Joseph S. Gawron G.L.O. Survey in 1953-1954. Peterson Cadastral Survey in 1966-1967.

Monument(s) & Accessories Found: (Condition and Source)

Found 1954 G.L.O. Brass Cap set firmly in ground.

38" Fir Stump, N82°E, 153.5' (No Marks), 1891 BT. Theil's 1891

Record N80½°E, 112.2'. Gesner's 1894 Record N81°E, 153.1'

45" Fir Stump, S81°E, 118.0' (No Marks), 1891 BT. Theil's 1891

Record S81½°E, 138.6'. Gesner's 1894 Record S81½°E, 116.8'


13" Hem. Stump, N14°W, 8.8' (Scribe Vis.), 1954 BT. Rec. N18°W, 9.2'

18" Hem. Stump, N55°E, 22.1' (Scribe Vis.), 1954 BT. Rec. N53½°E, 15.2'

Monument Detail

13" HEM. STUMP  
(SCRIBE VIS)

FD. 1954 G.L.O.  
BRASS CAP



Monument Set (Procedures and Description)

---



---



---



---

New Accessories

Set metal fence post beside brass cap. Wired survey attention sign to fence post.

Location & Comments

Corner lies on gentle South slope about 100' above road.

Compass Declination 20½  
Firm/Agency Roberts  
Surveying Inc.

Corner is in thick stand of 15-20 year old reproduction.  
Address 29 West 29th St.  
Eugene, Oregon 97405

Party Chief Les Roberts  
Notes Ted Baker

Witness Stu Duce

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Les Roberts*

OREGON  
AUGUST 22, 1975  
L. D. ROBERTS  
1039

*ok  
fcm*

C.S. File No. 58/280 <sup>6A</sup> <sub>(u)</sub>