

M 97-4

MINOR AND MAJOR LAND PARTITIONS
SUBDIVISIONS - CADASTRALS - SLOPE STAKING
PROPERTY AND LOT SURVEYS - ALTA'S

PROFESSIONAL MEMBERSHIPS:
PROFESSIONAL LAND SURVEYORS OF OREGON
AMERICAN CONGRESS ON SURVEYING AND MAPPING

AA SURVEYING SERVICE INC.

LICENSED IN: OREGON, WASHINGTON, CALIFORNIA AND ARIZONA

PHONE 1 - 503 - 672-2096

2498 OLD HWY. 99 S.

P. O. Box 130

ROSEBURG, OR 97470

SEE ACCOMPANYING MAP
SURVEY NARRATIVE

FILED *BS*
RECEIVED *BS*

JUN 28 1984

FOR: OREN STANDLEY
BY: AA SURVEYING SERVICE, INC.
DATE: JUNE 1984

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

PURPOSE:

Survey to set property corners and monument the East right-of-way line of road.

PROCEDURE:

The exterior corners of the NW 1/4 Section 36, Township 29 South, Range 9 West, W.M., Douglas County, Oregon were tied with a closed random traverse. I then subdivided the NW 1/4 per the 1976 Manual of Survey Instructions. I set the NW 1/16 and CW 1/16 corners in proper positions.

The East right-of-way line was calculated from the centerline information per instrument #83-15307 Douglas County Deed Records. Iron rods were set at the angle points of said East right-of-way line.

Bearings were based on a 1977 Stuntzner survey, Douglas County Surveyors Map File M63-61


EQUIPMENT:

Topcon GTS-2 #40423 and EDM

PERSONNEL:

David Stringer, LS
Karen Reed
Darrell Jones

Ron Quimby, LS
Mark Ramp



C.S. File No. 58/291-2