

M 78-19

OREGON CORNER RESTORATION FORM

Section 30 Township 19S Range 8W

County Douglas Date 1-09-85

Corner Designation

West 1/4 Corner  
Section 30 only.

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. 1957 G.L.O. Survey by Tillman and Survey M87-78 by Roberts Surveying in 1981.

Monument(s) & Accessories Found: (Condition and Source)

Found 1957 G.L.O. Brass Cap set firmly in ground.


44" Fir Stump, S20 1/4W, 43.0' (Scar Vis.) , 1891 BT. Rec. S20 1/2W, 43.6'

15" Maple , N48 3/4E, 24.2' (Scribe Vis.), 1957 BT. Rec. N48 3/4E, 23.8'

22" Hem. Snag, S11 3/4E, 11.7' (Scribe Vis.), 1957 BT. Rec. S11 3/4E, 11.9'

Monument Detail

Sketch



Monument Set (Procedures and Description)

See filed survey in Section 30.

New Accessories

24" Fir Stump, S78E, 30.4' to R.R. Spike (Painted/Aluminum Washer)

Set metal fence post next to brass cap. Wired land survey monument sign to fence post.

Location & Comments

Corner lies on gentle South slope. New logged unit lies to East. Compass Declination 20 1/2

Firm/Agency Roberts Surveying Inc.

Address 29 West 29th St.

Eugene, Oregon 97405

Party Chief Les Roberts

Notes \_\_\_\_\_

Witness Ted Baker

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Les Roberts*

OREGON  
AUGUST 22, 1975  
L. D. ROBERTS  
1039

# 25 T19-84  
# 40 T19-94

C.S. File No. 58/293