

M 96-63 A & B

FILED
RECEIVED *BS*

OREGON CORNER RESTORATION FORM


JUN 6 1984

Section 28 Township 21S Range 11W

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

County Douglas Date 4-16-84

Corner Designation



- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. _____
1982 Hintz M 93-47

Monument(s) & Accessories Found: (Condition and Source)


Fd. 3/4" I.R. set by Hintz LS 497 for W.C. 2.84 ft. East and 0.91 ft. South of true corner.

Fd. Hintz BT's to W.C.-28" D. Fir bears N 36° W 0.9 ft. to spike in face, healed face
23" D. Fir bears S 16 1/2° E 15.4 ft. to center vis. scribe.

Monument Detail

Set new W.C., 3" alum. cap in 2 1/2" x 30" alum. pipe with flared base bears N 88° 01' 14" E 15.12 ft. from true corner.

Sketch



Monument Set (Procedures and Description)

New Accessories

26" D. Fir bears N 46° E 17.3 ft. from W.C. scribed X BT

Set R.M.- to new W.C. corner-2 1/2" brass cap on 1" x 30" G.I. P. with flared base bears S 10° 00' 56" W 50.80 ft.

Location & Comments

Set from survey for U.S. Forest Service Compass Declination 19° 50' E
 Firm/Agency Jackson & Prochnau, Inc.
 Address P.O. Box 177
Albany, Ore. 97321
 Party Chief K. Kendall
 Notes _____
 Witness Larry Griensewic

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James W. Prochnau

OREGON
SEPTEMBER 21, 1977
JAMES W. PROCHNAU
1305