


COUNTY SURVEYORS  
 T275 R2W OFFICE  
 521 | 522  
 528 | 527  
 1977

DATE: <sup>10</sup>~~8~~-3-77

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewal #'s \_\_\_\_\_

Monument(s) Found: (Condition and Source) NONE



NOTE: APPROXIMATELY 150' N  
 OF THIS CORNER ARE TWO STUMPS  
 WITH B.L.M. B.T. SIGNS, & HEALED  
 BLAZES. I OPENED BOTH, & FOUND  
 THE SCRIBING NEARLY ALL DESTROYED.

THESE ~~ARE~~ MAY BE B.T.'S FROM DERRICKS  
 SURVEY. CREEK CALLED FOR IN G.I.O. NOTES

Accessories Found: (Condition and Source) RECORD, 653.4'

A 24" STUMP (WELL ROTTED) BEARS  
 N68°40'E, 49.5'. OPEN &  
 FIND SCRIBING & REVERSE, "22 BT".  
 ALL OTHER B.T.'S HAVE BEEN  
 DESTROYED BY LOGGING  
 ACTIVITIES.

#170v

NEW ACCESSORY:

A 6" DOUG. FIR BEARS S26°30'W,  
49.2' SCRIBED "T27S R2W S28  
CS BT" ON A DOUBLE BLAZE.

RENEWAL

Monument Set: (Procedure and Description) USING THE ONLY  
REMAINING B.T. STUMP FOR REFERENCE,  
I SET A 2 1/2" BRASS CAP ON A 1"  
GALV. IRON PIPE, STAMPED AS  
SHOWN ON REVERSE.

New Accessories: (Description) A 6" DOUG. FIR BEARS  
N83°W, 52.2' SCRIBED "T27S R2W S21  
CS BT" ON A DOUBLE BLAZE. A 9" DOUG.  
FIR BEARS N5°E, 19.1' SCRIBED "T27S R2W  
S22 CS BT" ON A DOUBLE BLAZE. A 9"  
DOUG. FIR BEARS S48°E, 20.9' SCRIBED  
"T27S R2W S27 CS BT" ON A DOUBLE BLAZE.

Location and Comments:

CORNER LIES  
~~AT~~ IN AN OLD  
CLEARCUT 200'  
EAST OF LOGGING  
SPUR.

20°E  
U.S.F.S.  
DENNIS GAYLORD  
"  
RANDAL LOPEZ

Compass Declination  
Agency  
Party Chief  
Notekeeper  
Witnesses

OK  
*[Signature]*