

DATE: 10-13-77

T 29 S R 7 W

	C	
N $\frac{1}{16}$		S 20
	C	

Condition Report On
 Not Found
 Renewed
 Unrecorded
 Surveyed In
 Referenced Out

Previous Renewal #'s NONE

Monument(s) Found: (Condition and Source) NONE

Accessories Found: (Condition and Source) NONE


~~250~~ #250 ✓

RENEWAL

Monument Set: (Procedure and Description) CORNER LOCATION DETERMINED BY SURVEY. AT THE CORNER POINT, WE SET A 1"x30" I. PIPE, 26" IN THE GROUND ON A STEEP WEST SLOPE, WITH BRASS CAP ATTACHED, MARKED:

DOUGLAS COUNTY SURVEYOR

T29S R7W



New Accessories: (Description) _____ 1977

AN 8" D. FIR, SCRIBED "CN 1/16 S 20 CS BT" ON A DOUBLE BLAZE,
BEARS S 23° E 31 3/4 FT..

AND A 12" I. CEDAR, SCRIBED "CN 1/16 S 20 CS BT" ON A DOUBLE BLAZE,
BEARS N 79° E 14 4/8 FT..

Location and Comments:
CORNER LOCATED APPROX,
70 FT. SOUTH OF AN E-W
FENCELINE,

20° EAST
DOUGLAS CO. SURVEYOR'S OFFICE
GARY L. LANGLITZ
Gary L. Langlitz
LARRY E. MONREAN
PETER L. EARLE

Compass Declination
Agency
Party Chief
Notekeeper
Witnesses