


PUBLIC LAND CORNERS

WEYERHAEUSER COMPANY
 SPRINGFIELD BRANCH



TOWNSHIP 26S RANGE 2 W
 SECTION 18 (only) CORNER S₁
 COUNTY Douglas OREGON

GLO SURVEY RECORD

DATE: 1918
 CORNER Brass Cap

PRESENT CONDITION - (DESCRIBE FULLY -
 USE PAGE 2 IF NEEDED FOR EXPLANATION.)

Found

ACCESSORIES:

	BEARING-	LINKS-	FEET-
(1) 36° Fir	N47E	17	11.2
(2) 18° Fir	N20W	58	38.3

30° Fir - rotted face, scribing visible.
 22° Fir - face healed over

Triangle Engr. SURVEY RECORD

DATE: 12/1974
 Found GLO 1918 Brass Cap & 2 Bts:
 (1) 24° Fir N49E 10.8"
 (2) 20° Fir N20W 37.0"

PRESENT CONDITION: 1/29/1976

30° Fir, rotted face; BT plate lowered to top of face.
 22° Fir, face healed over; "W" nail at base of tree; BT Plate lowered to top of face.


CORNER SET: GLO 1918 Brass Cap

MAG. DECL.: 20°

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY -	
N49E	10.8	GLO	Center of tree measurement
N19W	38.3		

SECTION 18 TOWNSHIP 26S RANGE 3W



 LINE MARKED BY NOTCH CUT IN BLAZE.

 KNOWN CORNER.

 REFERENCED CORNER
BY WEYERHAEUSER
METHOD.

This 1/4 corner is common only to Section 18.

ACCESSORIES ADDED THIS DATE: 1/29, 1976

MAGNETIC DECLINATION 20°

	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
↗ 44" Fir	S33W	26.1	--	X	X	--

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Rhododendron, Chinquapin

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) East ON MINUS (-) 65 %

NORTH: + 28% for 30' then descend

SOUTH: Level for 40' then descend

EAST: -65%

WEST: + 68%

FROM CORNER -

WORK DONE FOR W. CO. _____

FIELD NOTES IN BOOK: _____

BY: Glen McChesney DATE: 1/29/1976
Project ENGINEER - ~~SURVEYOR~~

UNDER THE SUPERVISION OF:

REGISTERED PROFESSIONAL LAND SURVEYOR

Frank O. Williams

OREGON JULY 12, 1968 FRANK O. WILLIAMS 0875

ASSISTED BY: _____

COPIES SENT TO: _____

C. S. File No. 59/4642 SEAL