

T 245

DATE: 4-3-78

32	33	R 2 W
5	4	

Condition Report Only
 Not Found
 Renewed
 Unrecorded
 Surveyed In
 Referenced Out

T 255

Previous Renewal #'s 1883, 1951, AND 1963 GOVERNMENT SURVEYS.

Monument(s) Found: (Condition and Source) _____

FOUND: 1951 GENERAL LAND OFFICE SURVEY BRASS CAP AND 1 1/2" I. PIPE

SET BY CALDER & WATSON (SEE WEYERHAEUSER NOTES). BOTH MONUMENTS

ARE OUT OF POSITION, DISPLACED BY LOGGING ACTIVITY.

Accessories Found: (Condition and Source) A 48" D. FIR, NOW A 54" STUMP

(Q.B.T.-1883), WITH ~~SCREWS~~ RESCRIBING "245 R 2 W 533 B" VISIBLE ON UNHEALED

BLAZE BEARS N 65° E 23 ⁸/₁₆ FT., (REC. N 65° E 16 ⁵/₁₆ FT.).

AN ORIGINAL 12" NOW 22" YEW (O.B.T.-1883), ALIVE, WITH RESCRIBING

"T 25 S R 2 W 55 B T" VISIBLE ON UNHEALED BLAZE, (NO ORIGINAL

SCRIBING FOUND) BEARS S 20° W 31 ⁷/₁₆ FT., (REC. S 15° E 33 ⁵/₁₆ FT.).

(O.B.T.-1883)

AN ORIG. 24" D. FIR, NOW A 37" SNAG NO SCRIBING FOUND, BEARS S 42° W

49 ⁵/₁₆ FT., (REC. S 40° W 49 ⁵/₁₆ FT.).

Page 1 of 1

110 T 25-2 ✓ # 98 T 24-2 ✓

C.S. 59/46-74

C

(O.B.T.-1883)

AND ORIG. 14" NOW 20" YEW ALIVE WITH FAINT SCRIBING "B" VISIBLE ON ORIGINAL
BLAZE AND RESCRIBING "T24S R2W S32 BT" VISIBLE ON UNHEALED
BLAZE BEARS N 26 1/2° W 16 5/8 FT. (REC. N 40° W 16 5/8 FT.)

WE DO NOT FIND THE SE BEARING TREE MARKED IN 1963, A 40" FIR

RENEWAL

Monument Set: (Procedure and Description) AT A LOCATION WHICH AGREES

WITH THE PREVIOUSLY DESCRIBED BEARING TREES, WE RESET THE 1951 G.L.O.

MONUMENT, A 2" X 36" I. PIPE, 30" IN THE GROUND, WITH BRASS CAP ATTACHED,

MARKED AS DESCRIBED IN THE OFFICIAL RECORD. WE ADD THE MARKINGS "CS 1978"

TO THE BRASS CAP AND PLACE THE 1 1/2" I. PIPE ALONGSIDE THE BRASS CAP,
EXTENDING 18" ABOVE GROUND.

New Accessories: (Description) WE CONFIRM THE BEARINGS AND

DISTANCES TO THE ACCESSORIES REFERENCED BY WEYERHAEUSER CO. AS

SHOWN ON PAGE 3 OF THE ATTACHED NOTES WITH THE FOLLOWING

EXCEPTION: A 20" YEW ~~BEAR~~ "W" NAIL BEARS S 20° W 30 1/2 FT.,

(WEYERHAEUSER RECORD S 20° W 30 5/8 FT.)

Location and Comments:

20° EAST

DOUGLAS CO. SURVEYOR'S OFFICE

GARY L. LANGRISH

Gary L. Langrish

STEPHEN J. FLAUSE

FRANK C. SILAGY

Compass Declination

Agency

Party Chief

Notekeeper


Witnesses

OK

PUBLIC LAND CORNERS

WEYERHAEUSER COMPANY
 SPRINGFIELD BRANCH


TOWNSHIP 25S RANGE 2W
 SECTION 4 CORNER NW
 COUNTY Douglas OREGON



GLO SURVEY RECORD Civil No. 60-135 DATE: <u>1963</u> CORNER <u>1951 GLO Brass Cap</u> set from original				PRESENT CONDITION - (DESCRIBE FULLY - USE PAGE 2 IF NEEDED FOR EXPLANATION.) <u>12/20/1975</u> Found	
ACCESSORIES: Original BTs, remarked 1951 & 1963					
	BEARING-	LINKS-	FEET-		
50" Fir	N65E	36	23.8	50" Fir stump, scribing visible;	
22" Yew	S20W	48	31.7	20" Yew, scribing visible. (BLM BT tag.)	
37" Fir snag	S40W	75	49.5	40" Fir snag, partial bark scribing.	
20" Yew	N26½W	25	16.5	20" Yew, scribing visible.	
New 1963	BT:				
40" Fir	S41½E	70	46.2	40" Fir stump, scribing visible, BLM BT tag.	
Weyerhaeuser SURVEY RECORD DATE: <u>11/20/1950</u> by D. Calder & R.D. Watson-Set 1½ iron pipe & put W nails & Weyerhaeuser plates on:				PRESENT CONDITION: <u>12/20/1975</u>	
48" Fir N71E 25.2'				Removed pipe & accessories referring to pipe.	
39" Fir S23E 38.8'				W. Co. plate gone, W nail overgrown- BLM BT tag.	
20" Yew S16W 28.8'				40" fir stump plate & W nail removed.	
16" Yew N15W 15.1'				Plate removed-new reference to W nail.	
				Plate removed-new reference to W nail.	
				BLM BT tag & new references refer to GLO brass cap.	
CORNER SET brass cap as found. Placed 1" pipe alongside on mound of stone.				MAG. DECL.: <u>20°</u>	

BEARING AND DISTANCE TO ABOVE IDENTIFIED SURVEY ACCESSORIES:

BEARING-	FEET-	SURVEY-	
N65E	23.8	Original	Center measurement.
S20W	31.7	"	" "
S40W	49.5	"	" "
N26W	16.5	"	" "
S42E	46.5	1963	" "



— // — // — // — LINE MARKED BY NOTCH CUT IN BLAZE.

○...KNOWN CORNER.

⊗...REFERENCED CORNER
BY WEYERHAEUSER
METHOD.

The GLO in 1951 & 1963 & Weyerhaeuser in 1950 found certain discrepancies in bearings and distances to the original record. The 1951 GLO Brass cap was set approximately 4' easterly of the Weyerhaeuser pipe. This pipe is now removed and any Weyerhaeuser Company accessories now refer to the GLO Brass Cap.

ACCESSORIES ADDED THIS DATE:

MAGNETIC DECLINATION 20°

	BEARING	FEET	ORIG. B.T.	"W" NAIL	PLATE	BRASS DISC
53" Fir Stump	S88E	9.0	---	X	X	---
20" Yew	S20W	30.5	X	X	X	---
20" Yew	N27W	15.3	X	X	X	---

IDENTIFIED ON PHOTO:

INFORMATION ON LOCATION OF CORNER AS NOW SET:

GROUND COVER: Salal, Vine Maple

(USING FORM LINES SKETCH TOPOG AT CORNER ON PAGE 2 PLAT)

SLOPE FACES (GIVE BEARING IN DEGREES) S65W ON MINUS (-) 27 %

FROM CORNER -

NORTH: + 35%

SOUTH: - 10%

EAST: + 35%

WEST: - 25%

WORK DONE FOR W. CO. _____

FIELD NOTES IN BOOK: _____

BY: Glen McChesney DATE: 12/20/1975
Project ENGINEER ~~REGISTERED~~

ASSISTED BY: _____

COPIES SENT TO: _____

UNDER THE SUPERVISION OF:

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Frank O. Williams

OREGON
JULY 12, 1968
FRANK O. WILLIAMS
0875

SEAL

PAGE 3

C.S. 59/46-74