

T275 R7W

DATE: 4-18-78

S.E. EXT. COR.
D.L.C. #48

<input type="checkbox"/>	Condition Report Only
<input type="checkbox"/>	Not Found
<input checked="" type="checkbox"/>	Renewed
<input type="checkbox"/>	Unrecorded
<input type="checkbox"/>	Surveyed In
<input type="checkbox"/>	Referenced Out

Previous Renewal #'s #43, M33-41

Monument(s) Found: (Condition and Source) A 1" IRON ROD (AT S.E. WIRE FENCE COR.) BEARS S77°W 1⁹ FT. FROM CORNER.

Accessories Found: (Condition and Source) (M 33-41) A 30" DIA. PINE STUMP, BADLY ROTTED, BEARS N42½°W (REC. N46°W) 68⁵ FT. A 8" NOW 23" DIA. (MEAS. BELOW FORK) W. OAK BEARS N79½°W 30⁴ FT. WITH "CSC 48" CARVED IN A PARTLY HEALED SINGLE BLAZE.

(REN. #48) A 10" DIA. LOCUST (MEAS. SOUTH FORK) BEARS N26°E 4² FT. WITH "SC 48 B" CARVED IN A PARTLY HEALED SINGLE BLAZE.

#190 ✓

RENEWAL

Monument Set: (Procedure and Description) I SET A 1"X36" IRON

PIPE WITH A BRASS CAP SET 5" ABOVE GROUND AND MARKED
~~5~~ "DOUGLAS COUNTY SURVEYOR"


T 27S R 7W
S.E. EXT
DLC 48

1978

New Accessories: (Description) NONE

Location and Comments:

<u>20°</u>	Compass Declination
<u>DCSO</u>	Agency
<u>R. B. KIMBERLING</u>	Party Chief
<u>R.B. Kimberling</u>	Notekeeper
<u>P.L. EARLE</u>	Witnesses
<u>F.C. SILAGY</u>	<u>OK</u> <u>JH</u>



COUNTY OF DOUGLAS
OFFICE OF THE SURVEYOR
ROSEBURG, OREGON 97470

April 25, 1978

Bureau of Land Management
William Glenn
P. O. Box 2965
Portland, OR 97208

Re: William Morin DLC #48, sections 13 and 24, T. 27 S. R. 7 W. W.M.

It is the finding of this office that the east and west boundary lines of DLC #48 are 10 chains + longer than shown on the original 1862 GLO plat and the original GLO field notes.

The evidence is based on our file maps M 33 - 41, James Byron, 1968; M 68 - 63, Glenn Baughman, 1978; and evidence found in the field by our corner renewal crews.

Maps and sketches are enclosed. Please contact this office if there are further questions.

Virginia A. Laugen
Virginia A. Laugen
Records Researcher
Douglas County Surveyors Office

cc: Commercial Title Company
Douglas County Title Company
Mountain Title Company
Trans America Title Company

CS FILE FOLDER

CONTAINS

MORE

INFORMATION

A COPY OF M33-41 WITH
CERTAIN CORNERS CIRCLED

A COPY OF THE CORNER RENEWAL
VISUAL SHOWING RENEWAL NUMBERS