


T 235 R 7 W



DATE: 11-28-78


- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewal #'s 13 AND 1965 RESURVEY

Monument(s) Found: (Condition and Source) A 2 1/2" IRON POST

WITH BRASS CAP MARKED

T 235 R 7 W



CAP WAS COVERED WITH TWO FEET LOOSE SHALE.

CAP LOCATED ON STEEP SLIDE AREA.

THIS CORNER IS CONTINUOUSLY BURIED BY
LOOSE SHALE

Accessories Found: (Condition and Source) A FIR, 5 INS. DIAM.,

NOW A 12 IN. BENT FIR, BEARS N. 47° E., 90.4
FEET DIST., WITH HEALED OVER SINGLE BLAZE.

A 17 INS. DIAM., NOW 20 IN DIAM. FIR BEARS
S. 63 1/2° E., 81.8 FEET, WITH HEALED OVER
DOUBLE BLAZE.

AN ALDER, 7 INS DIAM, NOW 12 IN. DIAM. BEARS

151 ✓

N. $12\frac{1}{2}^{\circ}$ W., 77.9 FT. DIST., WITH HEALED OVER

DOUBLE BLAZE. (1965 RESURVEY)

A 12" FIR BEARS S. $40\frac{1}{2}^{\circ}$ W., 23.1 FT. DIST.

WITH HEALED OVER DOUBLE BLAZE.

(~~1965 RESURVEY~~)

REN. # 13, 1940-N

ORIGINAL FIR SNAG NOT FOUND

RENEWAL

Monument Set: (Procedure and Description) LEFT CAP

IN POSITION.

New Accessories: (Description) MARKED ROCK

BLUFF WITH "BO +" WHICH BEARS N. 86° W.,

39.8 FT. LETTERS AND "+" APPROX. 6 INS. TALL.

Location and Comments:

GOR FALLS IN
MIDDLE OF SLIDE,
IN ROOSE SHAPE.

20° EAST

DCSO

GARY LANGLITZ

KAREN REED

GARY LANGLITZ

FRANK SILAGY

Compass Declination

Agency

Party Chief

Notekeeper

Witnesses

OK [Signature]