

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Established in 1928 by Ganong & Collins:

Set a 1" x 3' iron pipe 27" into ground with brass cap marked

1/4 S2
1928 from which:

- A 10" fir bears S45°E, 38 links (25.08 ft.)
- An 8" fir bears S26°W, 22 links (14.52 ft.)



Description of corner evidence found:

1" iron pipe with 2 1/2" brass cap attached marked:

U.S.G.L.O. Survey
T24S
R1E

Pipe is set loosely in ground. From which:

- A 12" Douglas-fir bears S26°W, 14.52 ft. Has a single healed blaze.
- A 17" Douglas-fir bears S45°E, 25.08 ft. This tree is still living, but all signs of a blaze have been destroyed by logging activities.

1/4 S2
T25S
R1E
1928

FILED
RECEIVED

APR 25 1979

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Description of monument and accessories I established to perpetuate the original location of this corner

I place a mound of stone around the iron pipe.

I mark a new bearing tree:

An 18" Douglas-fir bears S70°30'E, 35.4 ft. scribed "1/4 S2 BT" on double blazes.

Compass Declination: 18°E.

Corner 1/4 S35 T24S, R1E, bears east, 65.97 ft. (Record: N88°14'E, 96 lks or 63.36 ft.)

U.S.F.S. bearing tree signs were placed on all 3 B.T.'s. This corner is about 50 feet north of F.S. Road 2512.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1973
DENNIS L. GAYLORD
1636

I hereby certify the above corner monument was re-established as hereon described on April 19, 1979.

Witness: Bill West

Office of.....County Surveyor..... County of... Lane.....

State of... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 25 day of APRIL.....; 1979, at..... o'clock AM, (signed)

FRANCIS L. INGRAM..... by Virginia A. Langston (5/1/79)

(COUNTY OFFICIAL)

(DEPUTY)

#37 T25-1E X
#3 T24-1E X