

T 26 S R 6 W

DATE: 10/16/79

Condition Report Only

Not Found

X Renewed

Unrecorded

Surveyed In


Referenced Out

Previous Renewal #'s NONE

Monument(s) Found: (Condition and Source) FD. A 1" IRON PIPE

WITH BRASS CAP 16" OUT  
OF GROUND STAMPED

AS RECORDED BY  
BAUGHMAN (M 35-61)



Accessories Found: (Condition and Source)

FD A 20" DIA OAK STUMP 24" HIGH (REL  
20" DIA W. OAK) BEARS S 28° W 39 1/2 FT  
(REL S 26° 45' W 39 1/2 FT). LOWER  
BLAZE REMAINS PARTIALLY HEALED, "BT"  
SCRIBING VISIBLE

0101 ✓

AD: A 22" DIA. MADRONE (REC 16" DIA)  
BEARS N 87° E, 40° FT. (REC S 86° W  
40° FT) WITH A PARTIALLY HEALED DOUBLE  
BLAZE, SCRIBING SE 1/16 S16 BT VISIBLE  
CONTINUED ON P 3

RENEWAL

Monument Set: (Procedure and Description) LEFT AS FOUND

New Accessories: (Description) A 6" W OAK  
BEARS S 27° E 27 1/2 FT SCRIBED  
'SE 1/16 S16 CS BT" ON A DOUBLE  
BLAZE.

Location and Comments:

CORNER LIES  
SOFT NORTH  
OF DIRT ROAD  
COURSE E-W

20°  
D660  
PETE EARLE  
FRANK SILAGY

Compass Declination  
Agency  
Party Chief  
Notekeeper  
Witnesses

OK  
*[Signature]*

CONT  
FROM PG 2

DATE: 10/16/79

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewal #'s \_\_\_\_\_

Monument(s) Found: (Condition and Source) \_\_\_\_\_

Accessories Found: (Condition and Source) \_\_\_\_\_

THE BLAZE ON THIS MADRONE  
FACES THE PRESENT LOCATION OF THE  
BRASS CAP. THE BRASS CAP WAS FOUND  
FIRMLY SET IN GROUND. FOR  
THESE REASONS ALONG WITH THE AGREEMENT  
OF THE OTHER BEARING AND DISTANCES  
WE DETERMINE THIS BEARING TO THE MADRONE  
WAS RECORDED IN REVERSE

RENEWAL

Monument Set: (Procedure and Description) \_\_\_\_\_

New Accessories: (Description) \_\_\_\_\_

Location and Comments:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Compass Declination  
Agency  
Party Chief  
Notekeeper  
Witnesses