



RENEWAL

Monument Set (Procedure and Description)

Monument Detail

USING ALL FOUR ORIG. BT'S I SET 1" x 30" IP WITH BRASS CAP ATTACHED. THE COR. LOCATION MATCHES RECORD BEARINGS TO ALL FOUR BT'S AND FITS THE DISTANCES FAIRLY CLOSE IF THE DISTANCE IS TAKEN TO THE FACE OF THE TREE. BEARINGS AND DISTANCES USED TO SET COR. ARE AS FOLLOWS:

- 18" FIR STUMP BEARS N23E 24<sup>s</sup> TO FACE (REC 23<sup>e</sup>)
- 56" FIR STUMP BEARS S46<sup>1</sup>/<sub>2</sub>E 28<sup>3</sup>/<sub>4</sub> TO FACE (REC 27<sup>i</sup>)
- 47" FIR STUMP BEARS S47W 11<sup>9</sup> TO FACE (REC 11<sup>9</sup>)
- 13" HEMLOCK STUMP BEARS NSOW 8<sup>2</sup> TO FACE (REC 8<sup>s</sup>)

BRASS CAP PROTRUDES 12" OUT OF GROUND.

DOUGLAS CO SURVEYOR  
T 27 S  
S30 | S29  
S31 | S32

R8W

1982

New Accessories


SET SPIKE IN TOP OF SAID 18" FIR STUMP BEARS N23E 25<sup>2</sup> TO SPIKE

SET SPIKE IN TOP OF SAID 56" FIR STUMP BEARS S46<sup>1</sup>/<sub>2</sub>E 28<sup>3</sup>/<sub>4</sub> TO SPIKE

SET SPIKE IN TOP OF SAID 47" FIR STUMP BEARS S47W 12<sup>0</sup> TO SPIKE

SET SPIKE IN TOP OF SAID 13" HEMLOCK STUMP BEARS NSOW 9<sup>1</sup> TO SPIKE

Sketch of Monument, Accessories, and General Area



Location & Comments

Comp. Declin. 19° E  
Agency DCSO  
Party Chief GREGORY E. QUIBELL  
Notekeeper Gregory E. Quibell  
Witnesses KAREN REED

*Handwritten signature/initials*

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

*Gregory E. Quibell*

OREGON  
JULY 13, 1979  
GREGORY E. QUIBELL  
1834