

DATE: 4/6/82

Condition Report On
 Not Found
 Renewed
 Unrecorded
 Surveyed In
 Referenced Out

Previous Renewal #'s _____

T22S R10W Sec. 2, S.E. Corner

Monument(s) Found: (Condition and Source) _____

None found

Accessories Found: (Condition and Source) 15" D-Fir stump, 1' high,

with center rotten, brs. N50°E, dist. 6.63'

Note: The 15" stump 1 ft. high that was cut about two years ago, with the center rotten, has remains of a small flat face with ax marks visible behind a partially re-healed face that was cut out. County 41 growth rings to face. The snag was over 73 years old, and I also compared it with the found Original 15" D-Fir B.T. for the W 1/4 of Section 11, which was set at the same time. After establishing the corner point I ran a loop traverse between Sections 1 & 2, and also tied the Section corner to 35 & 36 T21S R10W, so I could compare (over)

Page 1 of 2

#85 X
C.S. File No. 61/32-1 C

calls and distance with G.L.O. notes (G.L.O. dist.: 6177.6')
 measured 6089.02'. The G.L.O. calls for two definite points
 from the North, one call for two creeks 52.8' apart and an-
 other call 1029.6' from the corner, "along W. slope and then
 along E. slope, divide course S80°W". Those check good. On
 the South it calls for a divide course NW, but the only divide
 is about 1000' away, but we have a spur 140' South of the

(Con't. pg. 2)

RENEWAL

Monument Set: (Procedure and Description)

Douglas County brass cap on 3/4" iron pipe, 36" long w/flanged
 bottom. Cap is marked: T22S R10W S2 S1 S11 S12 1982

New Accessories: (Description)

34" D-Fir stump, brs. N68°W, dist. 72⁵', scribed: T22S R10W S2

CSBT w/120 penny nail driven into top center, stamped: B0

30" D-Fir stump brs. S30°W, dist. 138³', scribed: T22S R10W S11

CSBT w/120 penny nail driven into top center, stamped: B0

31" D-Fir stump brs. S9°E, dist. 176⁸', scribed: T22S R10W S12

CSBT w/120 penny nail driven into top center, stamped: B0

Location and Comments:

LOCATION: Go along Rd.
 #210 approx. 1.4 miles.
 Corner area is ribboned
 and visible in large
 clearcut South of road.
 Location poster on
 Hemlock on North bank
 of road. From poster,
 corner lies South 625.

20°E
U.S.F.S.
Ernesto R. Alvarado
Carol Dickison
Colin Long

Compass Declination
 Agency
 Party Chief
 Notekeeper
 Witnesses

USFS Land
 Surveyor

OK
 JEM

Distances are to center of stumps.

DATE: 4/6/82

Condition Report Onl
 Not Found
 Renewed
 Unrecorded
 Surveyed In
 Referenced Out

Previous Renewal #'s _____

Monument(s) Found: (Condition and Source) _____

Accessories Found: (Condition and Source) (Con't. from pg. 1) _____

corner (G.L.O. call 82.5'). Calls going West to the 1/4 location
 fit reasonably well. I met on the ground with Douglas County
 Remonumentation crew and Harvey Wofford, Land Surveyor from
 B.L.M., Coos Bay to evaluate all the evidence found; a comment
 by Harvey was that he would hold to the evidence over pro-
 portional measurement.

4/6/82 Met with Douglas Co Remonumentation Crew

3/29/82 Met with Harvey Wofford, B.L.M. Land Surveyor

(Faint handwritten notes and scribbles)

CS 61/32-1

HORIZ	SLOPE DIST	VERT	TEMP	V DIST	RAW SLOPE	BRNG	Witnesses:	5
Found 3/18/82	T 22 S	R 10 W	Section 2	SE Corner			CAROL DICKISON	
1 1/2" D-Fir stump 1 FT high with the center rotten	1 FT						COLIN LONG	
2 GLO; Bxs N 50° E					4/6/82	met;	Douglas Remonumentation crew	
M Dist. 6 65					3/29/82		Harvey Wofford BLM Land Surveyor	
<p>The 15" stump 1 FT high that was cut about two years ago, with the center rotten, with remains of a small flat face with AX marks visible behind a partial re-head face that was cut-out. Counted 4 growth rings to face. The sawy was over 73 year old, and I also compared it with the found original 15" D-Fir B.T. for the W 1/4 of section 11, which was also set at the same time. After establishing the corner point I ran a loop traverse between section 1 & 2 and also tied the section corner to 35+36 T 21 S R 10 W, so that I could compare calls and distance with GLO Notes, (GLO Dist. 6177.6) measured 60.89. 02. The GLO calls for two definite points from the North, one call for</p>								
<p>Two creeks 52.8 FT apart and another call 102.6 FT. From the corner, "Along W. slope and then along E. slope, Divide course S 80° W". Those check good. On the south it calls for a Divide course ALLY, but the only divide is about 100 FT. away, but we have a spur 140 FT south of the corner (GLO call 82.5). Calls going west to the 1/4 location fit reasonably well. I met on the ground with Douglas County Remonument crew and Harvey Wofford, Land Surveyor from BLM Coos Bay to evaluate all the evidence found; A comment by Harvey was that he would hold to the evidence over proportional measurement.</p>								

Ernest R. Abner

JUN 2 1982

IN REPLY REFER TO

9600



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Coos Bay District Office
333 South Fourth Street
Coos Bay, OR 97420

JUN 1, 1982

Mr. Ernesto Alverado
USDA-Siuslaw National Forest
Mapleton Ranger Station
Mapleton, OR 97453

Dear Mr. Alverado:

After accompanying you to the corner of Sections 1, 2, 11, and 12, T. 22 S., R. 10 W., Will. Mer., it appears that the position you have established for the above mentioned section corner could very possibly be the position of the original corner. The one remaining possible bearing tree is now a fir stump, and was cut too low to recover any remaining scribe marks, but definite axe work was observed on the lower portion of a healed-over blaze. Upon counting the growth rings in the stump and considering the length of time since the area was logged, it is very possible that this is the stump of the original bearing tree.

This position also agrees with topography calls in three directions, and considering the distortion in the lines of the original surveyor in this area, and in the light of the amount of retracement you have done, this position would fit the topographic calls better than any other position, based on proportioning.

Sincerely yours,

Harvey E. Wofford
Harvey E. Wofford
Cadastral Engineer

18-0000061/32-1