

GOVERNMENT CORNER RESTORATION FORM

Township 31S Range 9W Section 2

County DOUGLAS State OR

Date 5-17-82 No. \_\_\_\_\_

Corner Designation T31S R9W  
1/4 S3|S2

Condition Report Only  
Not Found  
 Renewed  
Unrecorded  
Surveyed In  
Referenced Out



Previous Renewals #58

Monument(s) Found: (Condition and Source)  
FD. 1"x30" IP WITH BRASS CAP ATTACHED LYING  
ALONGSIDE ROOT WAD OF A LARGE FIR  
WINDFALL.

- Accessories Found:
- FD. ORIG. 10" MADRONE, NOW 12" STUMP HOLE WITH SMALL  
PORTION OF THE EASTERLY EDGE OF THE STUMP REMAINING.
  - FD. ORIG. 16" MADRONE, NOW 16" STUMP WITH CENTER AND FACE  
AREAS GONE.
  - FD. 6" MADRONE PER REN. #58, NOW 6" SNAG 4' TALL WITH  
SCRIBED "1/4 S2 CS BT" VISIBLE IN DOUBLE BLAZE.
  - FD. 8" MADRONE PER REN. #58 NOW 10" STUMP WITH PORTION  
OF HEALED OVER BLAZE VISIBLE.

Detail Found Monument

Detail Set Monument



Monument Set (Procedure and Description)

I RESET THE FD. BRASS CAP PER REN. #58 USING ALL FOUR  
FD. BT'S. BEARINGS & DISTANCES USED ARE AS FOLLOWS:  
ORIG. 10" MADRONE, NOW STUMP HOLE BEARS N 32E 22' (REC 22')  
ORIG. 16" MADRONE, NOW 16" STUMP BEARS N 29W 17' (REC 17')  
6" MADRONE PER REN. #58 BEARS N 50E 14' (REC N 51E)  
8" MADRONE PER REN. #58, NOW 10" STUMP BEARS N 75W 29' (REC N 77W)

BRASS CAP PROTRUDES APPROX 8" OUT OF GROUND.

New Accessories

7" FIR SCRIBED "1/4 S3 CS BT" IN DOUBLE BLAZE BEARS  
N 10°W 39.5 FT.  
48" FIR SCRIBED "1/4 S2 CS BT" IN DOUBLE BLAZE BEARS S 87E 25.5 FT.  
SET SPIKE IN TOP OF 8" MADRONE PER REN. #58, NOW 10" STUMP  
BEARS N 75W 29' TO SPIKE.

Location & Comments

Comp. Dec.

19° E

Agency

DCSO

Party Chief

GREGORY E. QUIBELL

Notes

GREGORY E. QUIBELL

Witnesses

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

GREGORY E. QUIBELL

OREGON  
JULY 13, 1979  
GREGORY E. QUIBELL  
1834

#1664  
S. P. No. 61/36-11

KAREN REED  
JOHN POWELL

