

0-4

SURVEY NARRATIVE
MYSTIC CREEK-CAMAS VALLEY SECTION
COOS BAY-ROSEBURG HIGHWAY
DOUGLAS COUNTY

FILED



NOV 18 1986

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

MAP Reference Drawing No. 9B-16-16

The purpose of this survey was to establish a new centerline for reconstruction of the Coos Bay-Roseburg Highway through the subject section. In connection with this survey, additional Highway right-of-way was established and monumented.



The survey was started by occupying U.S.C. & G.S. monument STANDLY and siting U.S.C. & G.D. monument CAMAS II. "Oregon State Grid Coordinates for Standly are N.508,096.15, E.1,147,540.01 and for CAMAS II N.503,752.84, E.1,123,568.36." Bearing of this line is S 79 43'49"W and this was the basis of bearings. The survey used grid bearings and grid coordinates (Oregon Grid South Zone). The survey traversed westerly closing into the control set in a previous 1973 O.S.H.D. survey mentioned in Douglas County Survey Filing Nos. M-6 and M-7.

This survey was conducted in the following areas:

NW $\frac{1}{4}$ Section 31 T29S.R8W.W.M.
SW $\frac{1}{4}$ Section 30 T29S.R8W.W.M.
NE $\frac{1}{4}$, SE $\frac{1}{4}$, SW $\frac{1}{4}$ Section 36 T29S.R9W.W.M.
NW $\frac{1}{4}$ Section 1 T30S.R9W.W.M.
NE $\frac{1}{4}$ Section 2 T30S.R9W.W.M.

The date of this survey was October 1982.
A survey supplement was done September 1986.

Oregon State Highway Division
P. O. Box 1128
Roseburg, Oregon 97470



C.S. 62/5 (N) - 6

N-8

SURVEY NARRATIVE
MYSTIC CREEK-CAMAS VALLEY SECTION
COOS BAY-ROSEBURG HIGHWAY
DOUGLAS COUNTY

MAP Reference Drawing No. 9B-16-16

FILED
RECEIVED *dh*

NOV 15 1983

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

The purpose of this survey was to establish a new centerline for reconstruction of the Coos Bay-Roseburg Highway through the subject section. In connection with this survey, additional Highway Right of Way was established and monumented.

The survey was started by occupying U.S.C. & G.S. monument STANDLY and siting U.S.C. & G.D. monument CAMAS II. "Oregon State Grid Coordinates for Standly are N.508,096.15, E.1,147,540.01 and for CAMAS II N.503,752.84, E.1,123,568.36." Bearing of this line is S 79 43'49"W and this was the basis of bearings. The survey used grid bearings and grid coordinates (Oregon Grid South Zone). The survey traversed westerly closing into the control set in a previous 1973 O.S.H.D. survey mentioned in Douglas County Survey Filing Nos. M-6 and M-7.

This survey was conducted in the following areas:

- NW $\frac{1}{4}$ Section 31 T29S.R8W.W.M.
- SW $\frac{1}{4}$ Section 30 T29S.R8W.W.M.
- NE $\frac{1}{4}$, SE $\frac{1}{4}$, SW $\frac{1}{4}$ Section 36 T29S.R9W.W.M.
- NW $\frac{1}{4}$ Section 1 T30S.R9W.W.M.
- NE $\frac{1}{4}$ Section 2 T30S.R9W.W.M.

The date of this survey was October 1982.

Oregon State Highway Division
P.O. Box 1128
Roseburg, Oregon 97470

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Martin G. Havig

OREGON
SEPT. 23, 1977
MARTIN G. HAVIG
1212

SEE FILED

OLD NARRATIVE 11/18/86

GLE No. 62/5