

RENEWAL

Monument Set (Procedure and Description)

Monument Detail

USING RECORD BEARING & DIST.
 FROM ED. "BT" (N44W 79² FT.)
 I RESET FOUND BRASS CAP IN
 ITS PROPER LOCATION. BECAUSE COR.
 FALLS ON VERY STEEP SLOPE AND
 ON SOLID ROCK I DRILL APPROX
 4" DEEP HOLE IN ROCK AND CEMENT
 IN A 5/8" x 30" IR; I THEN PUT
 THE ED. IP WITH BRASS CAP DOWN
 OVER SET IR AND CEMENT BOTTOM
 OF PIPE TO THE ROCK; I THEN
 PLACE A MOUND OF STONES AROUND
 THE MONUMENT. I ADD THE
 MARKS "RESET 1983" TO BRASS CAP.


RESET
 1983 | 1/4
 | S1
 T 26S R 8W
 1971

New Accessories

12" FIR SCRIBED "1/4S1 CS BT" IN DOUBLE BLAZE BEARS S40E 126² FT.
 7" FIR SCRIBED "1/4S2 CS BT" IN DOUBLE BLAZE BEARS S67W 27² FT.

Sketch of Monument, Accessories, and General Area

Location & Comments



Comp. Declin. 19°E
 Agency DCSO
 Party Chief GREGORY E. QUIBELL
 Notekeeper Gregory E. Quibell
 Witnesses RANDY SMITH
 JOHN POWELL

OK JM

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Gregory E. Quibell

OREGON
 JULY 13, 1979
 GREGORY E. QUIBELL
 1834