

RENEWAL

Monument Set (Procedure and Description)

Monument Detail

ON MARCH 3, 1983 MY CREW SET A 1" x 50" IP WITH BRASS CAP USING RECORD BEARINGS & DISTANCES FROM THE FOUND BEARING TREES AS FOLLOWS:

39" FIR STUMP BEARS N70E 36.3 FT.
 24" MADRONE BEARS N60E 80.6 FT.
 55" FIR STUMP BEARS N82E 46.0 FT.

SINCE THE BRASS CAP FALLS IN THE CENTER OF THE SLIDE AREA AND WILL PROBABLY BE WASHED OUT AGAIN, I RETURNED MARCH 23, 1983 AND SET TWO 5/8" IR WITH ALUMINUM CAPS AS REFERENCE MARKS. (SEE BELOW)

DOUGLAS CO SURVEYORS
 T30S R3W
 1/4 S27
 S34
 OFFICE


1983

New Accessories

"DOUGLAS CO."
 SURVEYOR

5/8" x 30" IR WITH ALUM CAP STAMPED "RM S 27" BEARS N45W 39.5.
 5/8" x 30" IR WITH ALUM CAP STAMPED "RM S 34" BEARS S45W 30.2.
 DOUGLAS CO.
 SURVEYOR

Sketch of Monument, Accessories, and General Area



Location & Comments

Comp. Declin. 19° E
 Agency DCSO
 Party Chief GREGORY E. QUIBELL
 Notekeeper " "
 Witnesses JOHN POWELL
RANDY SMITH

Surveyor's Seal
 REGISTERED PROFESSIONAL LAND SURVEYOR
Gregory E. Quibell
 OREGON
 JULY 13, 1979
 GREGORY E. QUIBELL
 1984