

GOVERNMENT CORNER RESTORATION FORM

Township T30S & T31S Range 1E Sec. 32 & 33, 4 & 5 County DOUGLAS

State OREGON Date APRIL 6, 1983 No: _____

Corner Designation


SECTION CORNER TO SECTIONS 32 & 33, T30S-R1E
AND 4 & 5, T31S-R1E.

- _____ Condition Report Only
- _____ Not Found
- Renewed
- _____ Unrecorded
- _____ Surveyed In
- _____ Referenced Out

Previous Renewals _____

Monument(s) Found: (Condition and Source)
2" D. IRON POST, 36" LONG, LYING ON THE GROUND,
SET BY G.L.O. IN 1923, WITH BRASS CAP MARKED AS
SHOWN.

MONUMENT DETAIL



Accessories Found:

ORIGINAL BLS:

- A- ROOTHOLE, N21°E, 1.6 FT. WITH DOWNED LOG ALONGSIDE WITH SCRIBE MARKS
T30S R1E S33 VISIBLE ON PARTIALLY HEALED BLAZE. (LOG IS 40" D. FIR).
- A- ROOTHOLE, S52°E, 14.5 FT. WITH 40" D. FIR STUMP ALONGSIDE WITH HEALED BLAZE.
- A- 36" D. FIR, S55°W, 21.8 FT. WITH HEALED BLAZE.
- A- 36" D. FIR STUMP, N33°W, 77.9 FT. WITH SCRIBE MARKS "R1E S32 B" VISIBLE ON
PARTIALLY HEALED BLAZE.

#47 T30-1E ✓

G.L.O. No. 6210-14 c

RENEWAL

Monument Set (Procedure and Description)

Monument Detail


THE ORIGINAL CORNER MONUMENT WAS KNOCKED OUT OF THE GROUND WHEN THE ORIGINAL NE BT BLEW OVER. AT A POSITION DETERMINED FROM RECORD BEARINGS & DISTANCES OF ALL ORIGINAL BTs, I RESET I.P. 32" IN THE GROUND IN A 2 FT. D. MOUND OF STONE. I STAMP "RESET 1983 L S 2024" ON BRASS CAP (5-18-83).

New Accessories

NEW BTs MARKED:

- A- 52" D. FIR, N49°E, 41.9 FT., SCRIBED "T30S R1E S33 CS BT" ON SINGLE BLAZE.
- A- 6" W. FIR, S85°E, 83.9 FT., SCRIBED "T31S R1E S4 CS BT" ON SINGLE BLAZE.
- A- 11" W. FIR, N31°W, 33.7 FT., SCRIBED "T30S R1E S32 CS BT" ON SINGLE BLAZE.

Sketch of Monument, Accessories, and General Area



Location & Comments

CORNER IS APPROXIMATELY 150 FT. WEST OF USFS ROAD #2925-670 in USFS CLEARCUT.

Comp. Declin. 18°E
 Agency U.S. FOREST SERVICE
 Party Chief JIM LANDRUM, L S 2024
 Notekeeper LEONARD HERZSTEIN
 Witnesses LEONARD HERZSTEIN

Surveyor's Seal
 REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Jim N. Landrum
 OREGON
 FEBRUARY 4, 1983
 JAMES N. LANDRUM
 2024