

GOVERNMENT CORNER RESTORATION FORM

Township 31S Range 1E Sec. 3, 4, 9 & 10 County DOUGLAS

State OREGON Date MAY 26, 1983 No. _____

Corner Designation

SECTION CORNER TO SECTIONS 3, 4,
9, AND 10, T31S, R1E.


- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals _____

MONUMENT DETAIL

Monument(s) Found: (Condition and Source)

2" DIAMETER IRON POST, FIRMLY SET, PROJECTING 2" ABOVE GROUND, WITH BRASS CAP MARKED AS SHOWN, SET BY G.L.O. IN 1923.



Accessories Found:

REMAINING ORIGINAL BTS:

A - 68" D. FIR, N41°E, 47 1/2 FT. WITH HEALED BLAZE.

A - 30" DECAYED FIR STUMP, S69°W, 25 1/2 FT. (REC. 24 1/2 FT.) WITH NO MARKS REMAINING.

A - 26" I. CEDAR, N40°W, 17 1/2 FT. (REC. 18 1/2 FT.) WITH SCRIBE MARKS "31S R1E S4" VISIBLE ON PARTIALLY HEALED BLAZE.

AND BT MARKED BY LEONARD CARTER G.L.O. IN 1936.

A - ROOT HOLE, S47°W, 67 1/2 FT. WITH 36" FIR STUMP ALONGSIDE WITH OLD AXE MARKS VISIBLE.
