


GOVERNMENT CORNER RESTORATION FORM

Township 28S Range 6W Sec. 18 County DOUGLAS

State OR Date 8/29/84 No. _____

Corner Designation




- _____ Condition Report Only
- _____ Not Found
- Renewed
- _____ Unrecorded
- _____ Surveyed In
- _____ Referenced Out

Previous Renewals # 223, # 243, CS 56/14 ^(T28-7) ^(T28-6)
~~#150~~ ~~+150~~

MONUMENT DETAIL

Monument(s) Found: (Condition and Source)
FD A BRASS CAP ON A I.P. FLUSH
WITH GROUND (PER REN #243) MARKED
AS NOTED

DOUGLAS COUNTY SURVEYOR



Accessories Found:

A 12" DOUBLE TRUNKED MAPLE WITH VISIBLE SCRIBING IN PARTIALLY HEALED
BLAZE ON EAST FORK "S R 7W S13 CS" BEARS N 11 1/2° W, 46.1 FT (REC.
N 9° W, 46.1') (PER REN #243).

A 19" NOW A 20" MAPLE WITH VISIBLE SCRIBING IN A PARTIALLY HEALED
SINGLE BLAZE "T28S R6W S18 CS BT" BEARS N 56° E, 159.8 FT
(REC. N 62° E, 158.9) IS TO SOUTHERLY MAPLE OF TWO MAPLES WHICH
ROOT CROWNS HAVE GROWN TOGETHER. (PER REN #243).

A 48" NOW A 46" COTTONWOOD WITH VISIBLE SCRIBING IN A PARTIALLY HEALED
DOUBLE BLAZE "28S R7W S13 CS BT" BEARS N 25° W, 21.7 FT (REC. N 22 1/2° W)
(PER REN #243).

A 47" NOW A 43" COTTONWOOD WITH A BOAT SPIKE 6 FT ABOVE GROUND
SPIKE BEARS S 47° E, 3.1 FT (REC. S 47° E). (PER REN #243)

I.P. PER REN #223 NOT FOUND I.P. PROBABLY REMOVED
WHEN FIELD WAS PLOWED.

#148 T. 28-6 X
 #256 T. 28-7 X

C.S. File No. 62/21-27

