

FILED

SR

MAY 2 1986

OREGON CORNER RESTORATION FORM

Section 22 Township 19S Range 8W

County Douglas Date 10-04-85

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Corner Designation

West $\frac{1}{4}$ Corner
Section 22

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. C.M. Collier's 1891 G.L.O. Survey and 1952 G.L.O. Dependent Resurvey.

Monument(s) & Accessories Found: (Condition and Source)

1952 G.L.O. Brass Cap setting loosely in the ground, having been disturbed by recent logging activity.

48" Fir Stump, S55E, 28.4' (Scar Vis.), 1891 BT. Rec. S55E, 28.4'

18" Maple, S29W, 35.3' (Scar Vis.), 1891 BT. Rec. S25W, 34.3'


20" Fir, S83W, 20.3' (Scar Vis.), ? BT.

Nail set in rock face, 23.7', 1985 R.P. Rec. 23.7'

"R.R." spike in root collar of 48" Fir Stump, S58E, 25.5'

Record S58E, 25.5', 1985 R.P.

Monument Detail



Monument Set (Procedures and Description)

Re-set 1952 G.L.O. Brass Cap firmly in ground. Buried purple magnetic marker under iron pipe. Set metal fence post, with survey attention sign wired to, beside brass cap.

New Accessories

Painted all B.T.'s red.

Location & Comments

Corner lies on steep West slope about 250' West of rock road in recently logged unit.

Compass Declination 20 $\frac{1}{2}$

Firm/Agency Roberts Surveying Inc.

Address 29 West 29th St. Eugene, Oregon 97405

Party Chief Ted Baker

Notes Stu Duce

Witness _____

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

Les Roberts

OREGON
AUGUST 22 1975
L. D. ROBERTS
1039

#29 X

C.S. File No. 62/30-50