


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The original section corner common to Sections 23, 24, 25 and 26, Township 29 South, Range 3 East, Willamette Meridian, Douglas County, Oregon, was established by Deputy Surveyor Herbert M. Raymond under contract No. 64, dated March 3, 1921.



FILED
jh

NOV 10 1986

COUNTY SURVEYOR
DOUGLAS COUNTY, OREGON

Description of corner evidence found:

At the corner point, I found a 2 1/2-inch diameter General Land Office monument marked as shown in diagram, and the following accessories:

A 40-inch diameter fir bears N.39°00'E., 36.1 feet distance, with a healed blaze.

A 48-inch diameter fir bears S.40°51'E., 24.1 feet distance, with a healed blaze.

A 44-inch diameter fir bears N.42°22'W., 25.4 feet distance, with a healed blaze. This tree is now dead and will be high-stumped during 1986 logging contract.

Description of monument and accessories I established to perpetuate the original location of this corner


I stabilized the monument as needed and marked the following accessories:

A 14-inch diameter fir bears S.14°42'W., 18.9 feet distance, scribed T29SR3ES26 LS1071 BT.

A 35-inch diameter cedar bears N.27°52'W., 77.3 feet distance, scribed T29SR3ES23 LS1071 BT.

October 8, 1986

HAROLD L. CENTER
Registered Professional Land Surveyor
Oregon Certificate No. 1071



Office of... Surveyor..... County of... Douglas.....
State of... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 10 day of... November....., 19 86, at..... o'clock.....m., (signed)
Fritz Ingram..... by *Virginia A. Raper*.....
(COUNTY OFFICIAL) (DEPUTY)

1A

FILED

jl

NOV 10 1986

SURVEY NARRATIVE TO COMPLY WITH
PARAGRAPH 209.250 OREGON REVISED STATUTES

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

SURVEY FOR: Rogue River National Forest
P. O. Box 520
Medford, OR 97501

LOCATION: Section Corner for Sections 23, 24, 25 and 26,
Township 29 South, Range 3 East, Willamette
Meridian, Douglas County, Oregon.

PURPOSE: To preserve and protect deteriorating corner evidence.

PROCEDURE: Utilizing existing corner evidence recovered at the
corner point, I verified the corner point from
recovered accessories, stabilized the monument and
marked additional accessories as required to
perpetuate the corner point.

BASIS OF BEARING: Solar Observation

DATE: October 8, 1986

HAROLD L. CENTER
Registered Professional Land Surveyor
Oregon Certificate No. 1071

