

GOVERNMENT CORNER RESTORATION FORM

Township 24S Range 1E Sec. 7 County DOUGLAS

State OR Date 7/2/86 No. \_\_\_\_\_

Corner Designation

$\frac{1}{4}$   
S12 | S7

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals NONE

Monument(s) Found; (Condition and Source)

A 24"X16"X10" BASALT STONE  
 MARKED "1/4" ON WEST FACE.  
 STONE IS TIPPED OUT OF POSITION  
 1.5 FT NORTH. (ORIG)

N/A

MONUMENT DETAIL

Accessories Found:

ORIG. BT'S

A 30" NOW 30" DIA. D.FIR SNAG WITH A SINGLE FULLY HEALED BLAZE BEARS S70°E, 9.9 FT (AGREES WITH REC.).

A 20" NW 24" DIA. 1 FT HIGH ROOTED D.FIR STUMP, NO BLAZE OR SKIBING FOUND, BEARS S64°W, 43.9 (REC. S64°W 44.9 IS A SLOPE MEASUREMENT).

#148 724-1W  
#9 724-1E

C

RENEWAL

Monument Set (Procedure and Description)

ORIGINAL PLUMB POS. OF ORIG. STONE REFERENCED, STONE IS REMOVED AND A 2 3/8" BC ON A 1/4" X 32" I.P. IS SET IN ITS PLACE PROTRUDING 1 IN. ABOVE A 2 FT DIA. 1 FT TALL MOUND OF STONE. ORIG. 24 X 16 X 10" BASALT STONE SET ALONG SOUTH EDGE OF I.P. WITH "1/4" MARK FACING WEST

Monument Detail

DOUGLAS COUNTY SURVEYORS  
T 245  
R 1/4  
W S12 | S7 R  
E  
1986  
OFFICE

New Accessories


8" DIA D. FIR DOUBLE BLAZED AND SCRIBED "1/4 S7 CS BT" BEARS N69°E, 14.8 FT.

4" DIA. T. CEDAR DOUBLE BLAZED AND SCRIBED "X BT" BEARS S22 1/2°E, 7.0 FT.

11" DIA. D. FIR DOUBLE BLAZED AND SCRIBED "1/4 S12 CS BT" BEARS S45 1/2°W, 32.5 FT.

11" DIA. D. FIR DOUBLE BLAZED AND SCRIBED "1/4 S12 CS BT" BEARS N09 1/4°W, 9.0 FT.

Sketch of Monument, Accessories, and General Area



Location & Comments

CORNER LIES APPROX. 250 FT NORTH OF THE NEW CORNER OF A NEW STEEP WESTERLY FACING CLEAR CUT APPROX 2 MILES ALONG USES ROAD 2300-600.

Comp. Declin. 18 1/2°E  
Agency DCSD  
Party Chief RANDALL W SMITH  
Notekeeper RANDALL W SMITH  
Witnesses STEPHEN J FLAUSE

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Larry E. Monrean*  
OREGON  
JULY 13, 1979  
LARRY E. MONREAN  
#1830