


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

THIS CORNER WAS RE-ESTABLISHED IN 1968 BY THE DOUGLAS COUNTY SURVEYOR'S OFFICE.



**FILED
RECEIVED** *fr*

MAY 23 1985

**COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.**

Description of corner evidence found:

FOUND A 2 1/2" BRONZE CAP ON A 1" IRON PIPE FROM WHICH;

- A DEAD OAK BEARS S80°E 95.2 FEET, ROTTED BLAZE.
- A 14" OAK BEARS S54°E 15.0 FEET, SCAR VISIBLE.
- A FIR STUMP BEARS S58°W 86.4 FEET, SCAR VISIBLE.
- A FIR STUMP BEARS S87°W 133.4 FEET, AXE WORK VISIBLE.
- A 26" OAK BEARS N83°W 147.5 FEET, SCAR VISIBLE.
- A 14" FIR BEARS N33°W 12.0 FEET, SCRIBE VISIBLE.
- A 50" OAK BEARS N14°E 101.8 FEET, SCAR VISIBLE.

Description of monument and accessories established to perpetuate the original location of this corner:

I MARKED A NEW 10" OAK B.T. WHICH BEARS S 47°W 9.4 FEET FROM THE SECTION CORNER, SCRIBED T30S R1W S15 BT.

FRIAR-MOFFIT & ASSOC.
717 W. 10TH ST.
MEDFORD, OR 97501



Office of..... Surveyor..... County of..... Douglas.....
 Oregon.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the...23... day of... May....., 19...85
 Fritz Ingram..... by..... *Virginia S. Ingram*.....
 (COUNTY OFFICIAL)..... (DEPUTY)

#227 X

C.S. File No. 63/8-14