

FILED
RECEIVED *JK*

AUG 2 1985

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Weyerhaeuser Company

Survey in Section 27, T.26 S., R.8 W, W.M.

Douglas County, Oregon

May 28, 1985

Map Reference *M99-18*

Weyerhaeuser Company conducted a survey in said section 27 to locate company property boundaries for timber-cutting purposes. Equipment used included a Topcon GT-3 EDM and accessories. Bearings were determined by solar observation. The GLO official plat showed said section 27 to be a regular section, and the survey subdivided said section 27 into aliquot parts.

The following information is a record of all corners found or set during the course of the survey:

S $\frac{1}{2}$ corner section 27:

Found; $1\frac{1}{2}$ " B.C.I.P. (Douglas Co. 1970) from which;
20" Fir BT bears N $67^{\circ} 00'$ E, 21.4 feet
72" Fir snag OBT bears S $24^{\circ} 00'$ W, 30.4 feet
22" Fir BT bears S $07^{\circ} 00'$ W, 20.3 feet (Rec. S07 00'E)

N $\frac{1}{2}$ corner section 27:

Found; $1\frac{1}{2}$ " B.C.I.P. (Juliano 1972) from which;
20" Fir BT bears N $43^{\circ} 30'$ W, 4.5 feet
24" Fir BT bears S $01^{\circ} 00'$ W, 26.6 feet

E $\frac{1}{4}$ corner section 27:

Found; $1\frac{1}{2}$ " B.C.I.P. ^{DCSO 9/11/85/18.} (BLM 1961) from which;
12" Fir stump BT bears N $44^{\circ} 30'$ W, 14.0 feet
15" Fir BT bears S $71^{\circ} 00'$ E, 6.8 feet

W $\frac{1}{4}$ corner section 27:

Found; 2" I.P. (#404) from which;
24" Fir BT bears N $49^{\circ} 00'$ E, 4.3 feet
24" Fir stump BT bears S $13^{\circ} 00'$ W, 11.9 feet

NE corner section 27:

Found; $\frac{3}{4}$ " steel screw-jack post, from which;
24" Fir BT bears S $61^{\circ} 00'$ E, 15.7 feet
18" Fir stump BT bears N $41^{\circ} 30'$ E, 11.7 feet
24" Fir BT bears N $40^{\circ} 15'$ W, 14.8 feet
22" Fir stump BT bears S $66^{\circ} 00'$ W, 30.0 feet

C.S. File No. 63/20 A

FILED
RECEIVED *SL*

AUG 2 1985

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

E 1/16 corner north line section 27:

Found; 3/4" I.P. (Juliano 1972) from which;
16" Madrone BT bears S 07° 00' W, 22.2 feet
30" Fir BT bears N 28° 00' W, 23.6 feet

NW corner section 27:

Found; 2" I.P. (#404) from which;
10" Chinkapin BT bears N 08° 45' E, 20.5 feet
14" Chinkapin BT bears N 61° 45' W, 28.4 feet
26" Fir BT bears S 15° 00' W, 46.2 feet
15" Fir BT bears S 55° 15' E, 37.0 feet

C 1/4 corner section 27:

Set; 3/4" I.P. (#1032) from which;
4" Fir scribed BT bears N 49° 30' W, 34.5 feet
12" Fir stump scribed BT bears N 71° 00' E, 2.1 feet
16" Fir scribed BT bears S 64° 30' E, 23.0 feet
12" Fir scribed BT bears S 14° 30' W, 11.0 feet

C-W 1/16 corner section 27:

Set; 3/4" I.P. (#1032) from which;
24" Fir scribed BT bears N 19° 00' W, 6.5 feet
22" Fir scribed BT bears N 69° 00' E, 29.0 feet

NW 1/16 corner section 27:

Set; 3/4" I.P. (#1032) from which;
22" Fir scribed BT bears N 68° 00' W, 32.5 feet
8" Fir scribed BT bears S 49° 00' E, 14.2 feet


C-N 1/16 corner section 27:

Set; 3/4" I.P. (#1032) from which;
34" Fir scribed BT bears N 23° 30' W, 15.2 feet
8" Fir scribed BT bears S 35° 00' W, 36.8 feet


NE 1/16 corner section 27:

Set; 3/4" I.P. (#1032) from which;
36" Fir scribed BT bears N 47° 00' W, 11.5 feet
26" Fir scribed BT bears N 24° 00' E, 5.0 feet

At the corners set, plastic caps with the surveyor's registration number were inserted into the top of the pipe. "W" nails were driven into the root collars of BT's, and the tags placed refer to the bearings and distances from nail to corner.



Michael S. McDowell



Respectfully submitted

Michael S. McDowell

Michael S. McDowell
P.L.S. 1032
P.O. Box 389
North Bend, Oregon 97459