

OREGON CORNER RESTORATION FORM

FILED

NOV 5 1986

Section 28 Township 29S Range 8W

County Douglas Date 10-15-86

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

Corner Designation

S.W. Sec. COR

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. SET BY HOWARD JOHNSTONE (#99)

IN 1961 BASED ON A CEDAR BEARING TREE SET FROM ORIGINAL ACCESSORIES, AND A 4x4 CEDAR POST FOUND.

Monument(s) & Accessories Found: (Condition and Source)

6" Cedar - Now rotting 5' tall snag - Bear's S25 1/4° E - 138 1/2 FT Scribe visible (1961)

6" W. FIR - Now down and rotted - Bear's N70 1/2° W - 118 3/4 FT - Scribing partially visible (1961)

12" W. FIR Bear's S80° W - 51 2/3 FT (Rec. 52° FT) Healed Face (1961)

14" Cedar Bear's N46° E - 126 60 FT Scribe visible (1961)

Monument Detail

Sketch

1/2" I.P. (Rec. 1" I.P.) extends 5" above grd (1961)

1/2" I.P.

Monument Set (Procedures and Description)

New Accessories

12" D. FIR Bear's S47° E - 28 1/2 FT scribed (T29S-R8W-S33 B.T.) (1986)

6" D. FIR Bear's N67° W - 23 1/2 FT Scribed (T29S-R8W-S29 - B.T.) (1986)

Location & Comments

Surveyor's Seal

Compass Declination N19° E

Firm/Agency CHAMPION

INTERNATIONAL


Address P.O. Box 1328

Roseburg OR.

Party Chief Dean Turner

Notes Lynn Sibley

Witness \_\_\_\_\_



C.S. File No. 6334-49 C

#2024