

M 115 - 50

SURVEY NARRATIVE

SURVEY FOR: Sun Studs, Inc.
P. O. Box 1127
Roseburg, OR 97470

DATE: May 1984

LOCATION: Section 32, Township 29 South, Range 9
West, Willamette Meridian, Coos County,
Oregon.


PURPOSE: To establish lines and set one-sixteenth
corners in the southwest quarter of
Section 32.

PROCEDURE: Found all existing corners necessary for
this survey. Closed a traverse through
these corners and determined bearings
and distances needed to set the corners
by intersection and proportionate measure-
ment. These corners were then set according
to the procedures as set forth in the 1973
"Manual of Surveying Instructions".


EQUIPMENT: This survey was executed with a Lietz
6-second Theodolite, a Lietz EDM, and
a Surveyor 31 computer.

BASIS OF BEARING: All bearings are based on the bearing of
the line from the one-quarter corner
between Sections 32 and 31 to the north
one-sixteenth corner between Sections 31
and 32 as determined by the Bureau of
Land Management Survey of 1982.

See map 33 B 20



Burton W. Holt



FILED *JH*

SEP 4 1992

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.