


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



**FILED** *JH*  
 MAY 5 1988  
 COUNTY SURVEYOR  
 DOUGLAS COUNTY, ORE.

Description of corner evidence found:

Found 2" iron pipe with 2 1/2" brass cap marked as shown in diagram and from which a original stone sets alongside, marked 1/4, from which:


- A 18" D. Fir stump bears N31°W, 11.9 feet. (visible scribe)
- A 20" D. Fir stump bears South, 16.5 feet. (visible scribe)
- A 15" D. Fir snag bears S71°E, 34.3 feet. (visible scribe)
- A 19" D. Fir snag bears N76°W, 3.0 feet. (visible scribe)
- A 12" D. Fir bears S69°W, 21.6 feet. (visible scribe)

Description of monument and accessories | established to perpetuate the original location of this corner

New Bearing Tree:

A 5" D. Fir bears N18°E, 31.6 feet, scribed "X" in small upper blaze and "BT" in small lower blaze. A 1/2" brass washer is nailed flush in lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on March 20, 1988. Bearing tree signs and monument signs were placed on all bearing trees without them and a 6" red band and face blazes were painted on all bearing trees.



Office of ..... Surveyor ..... County of ..... Douglas .....  
 State of ..... Oregon ..... , I hereby certify that the within instrument was filed in this office  
 for record on the ..... 5 ..... day of ..... May ..... 19 *88*, at ..... o'clock ..... m., (signed)  
 ..... Fritz Ingram ..... by ..... *Gerald V. Nygren* .....  
 (COUNTY OFFICIAL) (DEPUTY)

#230x