


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



**FILED**  
*[Signature]*  
 MAY 5 1988  
**COUNTY SURVEYOR**  
**DOUGLAS COUNTY, ORE.**

Description of corner evidence found:

Found 59" Sugar Pine (Angle Point) in good condition with 2 hack marks on each North and South sides, attention signs nailed to each North and South sides.

Description of monument and accessories established to perpetuate the original location of this corner

New Bearing trees:

A 18" D. Fir bears S22°W, 17.0 feet, scribed "T31S R3W S24 AP BT" with brass washer nailed to lower end of blaze.

A 10" D. Fir bears S22°E, 13.0 feet, scribed "T31S R2W S19 AP BT" with brass washer nailed to lower end of blaze.

Set aluminum post with boundary and monument signs 5 feet South of center of line tree.

I hereby certify the above corner point was perpetuated as hereon described on March 30, 1988. Bearing tree signs and monument signs were placed on all bearing trees and a 6" red band and face blazes were painted on all bearing trees.

**REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR**

*[Signature of Gerald V. Nygren]*

**OREGON**  
 GERALD V. NYGREN  
 AUGUST 22, 1975  
 1035

Office of Surveyor..... County of Douglas.....  
 State of Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the 5 day of May....., 1988, at ..... o'clock ..... m., (signed)  
 Fritz Ingram..... by Virginia Saenger.....  
 (COUNTY OFFICIAL) (DEPUTY)

X

U