


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



FILED *JK*
MAY 5 1988
COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Description of corner evidence found:

Found 2" iron pipe with 3" standard B.L.M. brass cap extending 8" above ground and marked as shown in diagram, from which:

- A 14" D. Fir Stump bears S58°E, 23.4 feet. (Blaze healed)
- A 9" D. Fir (dead & standing) bears S73°W, 22.4 feet. (blaze healed)

Description of monument and accessories I established to perpetuate the original location of this corner

New Bearing Trees:

- A 18" D. Fir bears S12°E, 72.5 feet, scribed "T33S R2W S5 BT".
- A 1/2" brass washer is nailed flush to lower end of blaze.
- A 9" W. Fir bears S42°W, 59.7 feet, scribed "T33S R2W S6 BT".
- A 1/2" brass whasher is nailed flush to lower end of blaze.

I hereby certify the above corner point was perpetuated as hereon described on April 21, 1988. U.S.F.S. bearing tree signs and monument signs were placed on all bearing trees without them and a 6" red band and face blazes were painted on each bearing tree.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Gerald V. Nygren
OREGON
GERALD V. NYGREN
AUGUST 22, 1975
1035

Office of Surveyor..... County of..... Douglas.....
State of Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 5..... day of May....., 19⁸⁸, at..... o'clock..... m., (signed)
Fritz Ingram..... by *Virginia Hansen*
(COUNTY OFFICIAL) (DEPUTY)