


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



FILED *JK*  
MAY 5 1988  
COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

Description of corner evidence found:

Found 2" Aluminum pipe with 2½" aluminum cap extended 6" above ground and marked as shown in diagram, from which:

- A 6" D. Fir stob bears S77°10'E, 39.7 feet. (visible scribe)
- A 7" D. Fir bears N16°35'W, 26.6 feet. (blaze healed)

Description of monument and accessories established to perpetuate the original location of this corner

New Bearing Tree:

- A 8" Madrone bears N72°W, 14.9 feet, bark scribed " C1/4 S8 BT".
- A ½" brass washer is nailed flush to lower end of scribing.

I hereby certify the above corner point was perpetuated as hereon described on April 15, 1988. Bearing tree signs and monument signs were placed on all bearing trees without them and a 6" red band and face blazes were painted on all bearing trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Gerald V. Nygren*  
OREGON  
GERALD V. NYGREN  
AUGUST 22, 1975  
1035

Office of Surveyor ..... County of Douglas  
Oregon  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the 5 day of May, 1988, at ..... o'clock ..... m., (signed)  
Fritz Ingram by *Gerald V. Nygren*  
(COUNTY OFFICIAL) (DEPUTY)

#224 \*