


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



FILED

NOV 30 1988

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE.

Description of corner evidence found:

A brass cap on iron pipe marked as shown in diagram, from which:

#86 T.27-2
#52 T.28-2

- A 6' high, 32" hemlock stump bears N67°E, 13.9 feet - visible scribing
- A 9" yew, dead and broken off 4' above ground bears N17°W, 10.6 ft. - visible scribing
- A 54" D. fir, 4' high stump, bears N1°W, 13.2 ft. - visible scribing.

*What AP?
200' E of N1/4 Cor
500' 2*

Description of monument and accessories established to perpetuate the original location of this corner:

- (New BT's) 8" hemlock, S20°W, 11.0 feet, scribed "AP BT"
- 18" double yew, S70°W, 39.1 feet, scribed, "AP BT"
- Set 1/2" brass washers in BT faces marked "LS 1035".

I hereby certify that the above corner was perpetuated as hereon described on October 20, 1988. Bearing tree and monument signs were placed on all BT's without them and a 6" red band and face blazes were painted on all bearing trees.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
GERALD V. NYGREN
AUGUST 22, 1975
1035

Office of..... Surveyor..... County of Douglas.....
 State of..... Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the...30... day of...November....., 19..88
 Fritz Ingram..... by Virginia C. Sawyer.....
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

#254 T.27-2 +
#146 T.28-2 +

C.S. File No. 63/69-300