

Mail:
1140 ACACIA LANE
GRANTS PASS, OR 97528

M 106-21

TELEPHONE 476-3269

ROBERT M. THOMPSON
Consulting Engineer, Surveyor, Forester

Office:
233 N. E. "B" STREET

SURVEY TO LOCATE PART OF THE SOUTH LINE OF THE
NE $\frac{1}{4}$ SE $\frac{1}{4}$ OF SECTION 19, T32S, R6W, W.M., DOUGLAS CO., OR

FILED

RT

JUN 2 1988

Narrative description to comply with Par. 209.250, O.R.S.

by: Robert M. Thompson, 1140 Acacia Lane, Grants Pass, OR 97527.

COUNTY SURVEYOR
DOUGLAS COUNTY, ORE

for: Billy Blommé, 1879 McCullough Creek Rd., Glendale, OR 97442.

Purpose: To locate and mark that part of the South line of the NE $\frac{1}{4}$ SE $\frac{1}{4}$ lying west of McCullough Creek and Shepard Creek, being Blomme's south boundary.

Note: One map sheet accompanies this narrative.


Procedure: Oregon State Board of Forestry Survey No.M 71-79 done in 1978, had set monuments to mark or witness the Southwest and Southeast corners of said NE $\frac{1}{4}$ SE $\frac{1}{4}$, but not marked the line between them. Blommé's southerly boundary, considering a 1970 conveyance to Shepard, followed creeks on the East side of the McCullough Creek County Road, and the South line of said "forty" on the West side of said road. My Survey traversed and computed the true South line of said "forty" using said Survey No.M 71-79 for bearing control. That portion of said South line lying west of, and within said road right-of-way, was then marked with red-painted blazes and "glo-top" stakes. It was noted that the West line of said NE $\frac{1}{4}$ SE $\frac{1}{4}$ was found to be blazed and posted with O.S.B.F. signs, as indicated on Survey File No. M71-79. Corner data found is as follows, B.T.'s Meas. to face locations: SE1/16 Cor. Found O.S.B. F. brass cap on 1 $\frac{1}{2}$ " G.I. Pipe, 4" x 4" post, & B.T.'s:

28" D Fir N 34°E 23.3' to healed face
9" Chinquapin N 65°W 29.1' visible scribe

S 1/16 Cor. Secs. 19 & 20 Found O.S.B.F. brass cap on 1 $\frac{1}{2}$ " G.I. Pipe witness mon. being S 01°07'01" W 20.0' from true pos'n. on south bank of Blommé Creek, 4" x 4" post, & witness mon. B.T.'s:

21" Grand Fir N 25°W 16.9' to healed face
21" D. Fir S 57°E 52.3' to healed face

Jan. 28, 1988



LAND SURVEYING

ROADS

BRIDGES

DAMS

TRACT DESIGN

FOREST MANAGEMENT

TIMBER CRUISING AND APPRAISAL

C.S. File No. 63/75