


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



FILED



AUG 7 1989

COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE.

Description of corner evidence found:

Found 1 1/2" iron pipe with 3" brass cap extended 4" above stone mound and marked as shown in diagram, from which bears:


- A 30" D. Fir, S62 1/4°W, 92.5 feet (healed blaze)
- A 24" Fir snag, S84°E, 33.0 feet (vis. scribe)
- A 32" D. Fir, N35 1/2°W, 57.8 feet (vis. scribe)
- A 8" D. Fir, N70 1/4°E, 26.5 feet (healed blaze)
- A 12" D. Fir, S1 E, 25.1 feet (healed blaze).

Description of monument and accessories established to perpetuate the original location of this corner

(New BT) A 8" D. Fir, S84°E, 22.6 feet scribed "T32S R1W S23 BT" with 1/2" dia. brass washer marked "LS 1035" nailed to lower blaze.

I hereby certify the above corner was perpetuated as hereon described in July, 1989. Bearing tree signs and monument signs were placed on all BT's without them and a 6" band and face blazes were painted with red paint on all bearing trees.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR



OREGON  
GERALD V. NYGREN  
AUGUST 22, 1975  
1035

Office of Surveyor..... County of Douglas.....  
 State of Oregon....., I hereby certify that the within instrument was filed in this office  
 for record on the 7 day of August, 19 89, at o'clock .m., (signed)  
 Fritz Ingram by Virginia C. Lingen  
 (COUNTY OFFICIAL) (DEPUTY)

#1064

Form R6-7100-57 (9/66)

G.S. File No. 63/85-21