

Township 33 S Range 7 W Sec. 8 County DOUGLAS

State OR Date 10-20-92 No. _____

OCT 30 1992

Corner Designation

1/4 S8 | S9

COUNTY SURVEYOR

DOUGLAS COUNTY, ORE.

Condition Report Only

Not Found

Renewed

Unrecorded

Surveyed In

Referenced Out

MONUMENT DETAIL

Previous Renewals 38, 1975 BLM D. RESURVEY

Monument(s) Found: (Condition and Source)

2 1/2" DIA DCSG BRASS CAP ON
A 1 1/2" O.D. IRON PIPE PROTRUDING
8 IN. ABOVE GROUND. (REN #38)

14" NOW 16" DIA 2 FT HIGH STUMP
NO MARKS VISIBLE (ORIG. COR. TREE)

DCSO BC/1P BEARS WEST 110 FT
FROM CORNER TREE (AGREES
WITH 1975 BLM D. RESURVEY

COUNTY SURVEYORS OFFICE

T 33 S R 7 W

1/4 S8 | S9 DOUG
JOS. CO. CO.

1968

Accessories Found:

18" NOW 14" D. FIR SNAG WITH SCRIBE MARK VISIBLE. "S" HAS
A HEALED LOWER BLAZE, BEARS EAST 3.8 FT
(AGREES WITH 1975 BLM REC) ORIG. BT

14" NOW 15" DIA. D. FIR SNAG WITH A HEALED BLAZE
BEARS S51°W, 15.8 FT (REC S48°W, 15.8 FT)
ORIG BT

26" NOW 24" DIA. D. FIR WITH A PARTIALLY HEALED SINGLE
BLAZE SCRIBING VISIBLE "1/4 S8 CS BT" BEARS S35°W,
19.5 FT (REC S35°W 19.8 FT) REN #38

39" NOW 42" DIA. D. FIR WITH A FULLY HEALED SINGLE
BLAZE BEARS N20°E, 24.4 FT (AGREES WITH 1975
BLM REC) REN #38

1975 BLM BT S40°W, 39.6 FT IS GONE

#464

Monument Set (Procedure and Description)

Monument Detail

NONE

N/A

New Accessories

4" MADRONE BARK SCRIBED "Y458CS BT"
BEARS S56°W, 19.2 FT

19" D. FIR SINGLE BLAZED "Y459CS BT"
BEARS N45°E, 50.5 FT


Sketch of Monument, Accessories, and General Area

Location & Comments

CORNER LIES IN A STEEP
SLIDE AREA APPROX
50 FT WEST OF ROAD

Comp. Declin. 18° E
Agency OCSO
Party Chief RANDALL W SMITH
Notekeeper Randall W Smith
Witnesses STEPHEN J FLAWE

Address



REG SURVEYOR'S Seal
PROFESSIONAL
LAND SURVEYOR

Randall W Smith

OREGON
JULY 25, 1990
RANDALL W. SMITH
2469