


GOVERNMENT CORNER RESTORATION FORM FILED

Township 31S Range 8W Sec. 19 County DOUGLAS

State OREGON Date Nov, 1992 No. \_\_\_\_\_

DEC 14 1992

Corner Designation



COUNTY SURVEYOR  
DOUGLAS COUNTY, ORE

- \_\_\_\_\_ Condition Report Only
- \_\_\_\_\_ Not Found
- Renewed
- \_\_\_\_\_ Unrecorded
- \_\_\_\_\_ Surveyed In
- \_\_\_\_\_ Referenced Out


Previous Renewals NONE, 1962 BLM RESURVEY

Monument(s) Found: (Condition and Source)

FROM 1962 BLM RESURVEY.  
A 3 INCH DIAMETER BRASS CAP MARKED AS AT  
RIGHT ON 2 1/2 INCH O.D. IRON PIPE FIRMLY SET  
AND PROTRUDING 6 INCHES ABOVE GROUND.

MONUMENT DETAIL

U.S. DEPT. OF THE INTERIOR



Accessories Found:

ONE ORIGINAL BEARING TREE FOUND A FIR, 24 INS. DIAM., NOW  
A 34 INCH D.B.H DOUGLAS FIR WITH A FULLY HEALED DOUBLE BLAZE BEARS  
N71°E, 48<sup>2</sup> FEET DISTANT (RECORD N71°E, 47<sup>5</sup> FEET, A FACE MEASUREMENT).

TWO BEARING TREES FROM BLM RESURVEY RENEWAL. A FIR, 12 INS.  
DIAM., NOW A 19 INCH D.B.H. DOUGLAS FIR WITH A FULLY HEALED DOUBLE BLAZE  
BEARS N18 1/4°E, 7<sup>2</sup> FEET DISTANT (AS PER RECORD).  
A FIR, 12 INS. DIAM., NOW A 17 INCH D.B.H. DOUGLAS FIR WITH A FULLY HEALED DOUBLE  
BLAZE BEARS N86 1/2°W, 40<sup>2</sup> FEET DISTANT (RECORD N86 1/2°W, 41<sup>2</sup> FT. DISTANCE TO  
CENTER OF TRUNK LEVEL WITH CAP).  
BOTH TREES HAVE A SMALL UPPER BLAZE AND A LARGE LOWER BLAZE.

31-8 = # 83 x

31-9 = # 179 x

