

GOVERNMENT CORNER RESTORATION FORM

Date: 5/31/94 By: X

Township 21S Range 5W Sec. 4 County DOUGLAS

This survey consists of: \_\_\_\_\_

State OR Date 3-31-94 No. \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpts 564/51

Corner Designation

1/4 S 5/54

DOUGLAS COUNTY

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals NONE

MONUMENT DETAIL

Monument(s) Found: (Condition and Source)

NAIL SET BY LES ROBERTS

N/A

Accessories Found:

20" NOW DOWN AND ROTTING D. FIR OF INDETERMINABLE SIZE WITH SCRIBING FOUND "S 1/4 BT" BEARS N 75° W, 2.0 FT (AGREES WITH ORIG. REC AND NAIL BY LES ROBERTS).

ORIG. SE BT NOT FD.

RENEWAL

Monument Detail

Monument Set (Procedure and Description)

2 3/8" DIA DCSO BRASS CAP ON A  
 1 3/8" BY 32" LONG IRON PIPE IS  
 SET AT REFERENCED POSITION OF  
 NAIL. BEJIP PROTRUS 5"  
 ABOVE GROUND.

DOUGLAS COUNTY SURVEYORS

T 21 S


1/4 R  
 S5/S4 5  
 W

1994  
 OFFICE

New Accessories

8" DIA D.FIR DOUBLE BLAZED AND SCRIBED "1/4 S 4 C S BT" BEARS  
 N 6 1/2° E 12.8 FT  
 12" DIA D.FIR DOUBLE BLAZED AND SCRIBED "1/4 S 4 C S BT" BEARS  
 S 71° E 10.9 FT  
 15" DIA D.FIR DOUBLE BLAZED AND SCRIBED "1/4 S 4 C S BT" BEARS  
 S 29 1/2° W 10.6 FT  
 12" DIA D.FIR DOUBLE BLAZED AND SCRIBED "1/4 S 4 C S BT" BEARS  
 N 83° W 13.5 FT

Sketch of Monument, Accessories, and General Area



Location & Comments

CORNER LIES ON TOP  
 OF A NORTH - SOUTH  
 RIDGE APPROX 100 FT  
 WEST OF A DIRT ROAD

Comp. Declin. 18° E  
 Agency DCSO  
 Party Chief RANDALL W SMITH  
 Notekeeper *[Signature]*  
 Witnesses STEPHEN J FLAVUS

Address

Surveyor's Seal

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Randall W Smith*  
 EXP. 12-31-94

OREGON  
 JULY 25, 1990  
 RANDALL W. SMITH  
 2489