

GOVERNMENT CORNER RESTORATION FORM

Date: 6-16-94 By: JD

Township 28S Range 7W Sec. 7

County DOUGLAS This survey consists of:
Map: _____

State OR Date 5-23-94 No. _____

Narrative: _____
Corner Rpt: C.S. 64/51

Corner Designation

1/4 S 7 | S 8

PI# 200540

Previous Renewals 1924 MENSCH, 1961 BYRON

Monument(s) Found:	(Condition and Source)
<u>2 1/2" DIA. BRASS CAP ON A 1 1/2" O.D. IRON PIPE, PROTRUDES 16" ABOVE GROUND. (1961)</u>	
<u>1" I.D. IRON PIPE, PROTRUDING 3" ABOVE GROUND IS FOUND ALONG SOUTH EDGE OF BC/IP.</u>	

- DOUGLAS COUNTY SURVEYOR Only
- Condition
 - Not Found
 - Renewed
 - Unrecorded
 - Surveyed In
 - Referenced Out

MONUMENT DETAIL

COUNTY SURVEYORS
T 275 R 8W

1/4 S 7 | S 8

1961 OFFICE

Accessories Found:

18" NOW 1 FT HIGH ROTTED OAK STUMP OF INDETERMINABLE SIZE, OLD AXE MARKS AND BLAZE VISIBLE, NO SCRIBING FOUND BEARS S 30° E, 52.1 FT (AGREES WITH 1961 BYRON REC.) O.B.T.

30" NOW 40" DIA LIVE 30 FT HIGH MACHINE SNAG, SHOWS EVIDENCE OF A PREVIOUSLY OPENED NOW BURIED OUT BLAZE NO SCRIBING FOUND, BEARS S 78° W, 19.2 FT (REC S 78° W, 17.8 FT) O.B.T.

16" NOW 24" DIA, 3 1/2 FT HIGH D. FIR STUMP WITH A FULLY HEALED SINGLE BLAZE, BEARS S 43° E, 14.5 FT (REC S 40° E, 14.5 FT) 1924

6" NOW 17" DIA D. FIR WITH A FULLY HEALED SINGLE BLAZE, BEARS N 17° W 15.2 FT (AGREES WITH REC) 1924

RENEWAL

Monument Set (Procedure and Description)

1961 BC/IP MISS MARKED, WE
MARK BC TO SHOW CORRECT
TOWNSHIP AND RANGE.

Monument Detail

COUNTY SURVEYORS
T28S R7W


1/4 S7/S8

1961
OFFICE

New Accessories

- 22" DIA. D. FIR DOUBLE BLAZED AND SCRIBED " 1/4 S7 CS BT "
- BEARS S 37 1/2° W, 8.0 FT
- 6" DIA. W. FIR DOUBLE BLAZED AND SCRIBED " 1/4 S8 CS BT "
- BEARS N 51° E, 9.0 FT
- 6" DIA. CEDAR DOUBLE BLAZED AND SCRIBED " 1/4 S7 CS BT "
- BEARS 'N 64° W, 33.5 FT

Sketch of Monument, Accessories, and General Area



Location & Comments

CORNER LIES 30 FT
SW OF A DIRT RD.

POSITION OF CORNER APPEARS
TO HAVE BEEN DETERMINED
BY MENSCH AT A INTERSECTION
OF ORIG. DIST. EVIDENCE IN
FIELD DEPICTS BLAZES FACING
BC/IP

Comp. Declin. 17 3/4° E
 Agency DCSG
 Party Chief RANDALL W. SMITH
 Notekeeper Randall W. Smith
 Witnesses STEPHEN J. FLAUS

Address

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Randall W. Smith
EXPIRES 12-31-94

OREGON
JULY 25, 1960
RANDALL W. SMITH
2982