

GOVERNMENT CORNER RESTORATION FORM

Date: 12-29-94 By: JP

Township 31S Range 6W Sec. 31 County DOUGLAS

State OR Date 8-4-94 No. Corner Exp. 64/52

Corner Designation

1/4 536 | 531

- DOUGLAS COUNTY
- Condition: Surveyor Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

100140

Previous Renewals M 33-49, #56

Monument(s) Found:	(Condition and Source)
1 1/4" I.D. IRON PIPE LEANING 8" EAST OF PLUMP. PROTRUDES 5" ABOVE GROUND. (M 33-49)	
2 1/2" BRASS CAP ON A 1 1/2" O.D. BY 36" LONG IRON PIPE IS FOUND LAYING ON TOP OF GROUND NEAR ABOVE SET I.P. BC/IP SHOWS NO EVIDENCE OF HAVING BEEN SET. (REN#56)	

COUNTY SURVEYORS OFFICE

T 31 S
 R 7 S36 | 531 R
 W W

1966

Accessories Found:

- O.B.T.'S FROM 1882
- 20" NOW 28" DIA. 3 FT HIGH D.FIR STUMP WITH EVIDENCE OF OLD BARK SCRIBING "1/4" AND PARTIALLY HEALED SINGLE BLAZE WITH SCRIBING VISIBLE "1/4 S36" BEARS N 34° W, 15.2 FT (AGREES WITH RECORD) O.B.T.
- 16" NOW 19" DIA. D.FIR WITH A FULLY HEALED DOUBLE BLAZE, NO BARK SCRIBING VISIBLE, BEARS N 58° E, 15.8 FT (AGREES WITH REN#56) O.B.T.
- 6" YEW WOOD WITH A SINGLE BLAZE SCRIBED "1/4 BT" BEARS N 44° E, 24.0 FT (AGREES WITH REC)
- 30" D.FIR WITH A SINGLE BLAZE SCRIBED "1/4 BT" BEARS S 58° E, 23.5 FT (AGREES WITH REC)
- 28" D.FIR WITH A SINGLE BLAZE SCRIBED "1/4 BT" BEAR S 38° E, 47.6 FT (REC S 35° E, 47.6 FT)

RENEWAL

Monument Set (Procedure and Description)

Monument Detail

1/4" I.D. IRON PIPE IS REFERENCED AND REMOVED, MEASURES 24" LONG 1966 DCSO BC/IP IS SET AT REFERENCED POSITION, THE MARKS "RESET 1994" ARE ADDED TO BRASS CAP. BC/IP PROTRUDES 9" ABOVE GROUND. 24" IRON PIPE IS SET ALONG NORTH EDGE OF BC/IP, PROTRUDE 7" ABOVE GROUND

COUNTY SURVEYORS OFFICE
T 315
R 7 536/531 R
W W
RESET 1994
1966


MONUMENTS ARE SURROUNDED BY A 24" DIA. 9" HIGH MOUND OF STONE

New Accessories

NONE

Sketch of Monument, Accessories, and General Area

Location & Comments



Comp. Declin. 173/40E
Agency DCSO
Party Chief RANDALL W SMITH
Notekeeper Randall W Smith
Witnesses STEPHEN J FLAUS

Address

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Randall W Smith
EXPIRES 12-31-94

OREGON
JULY 25, 1990
RANDALL W. SMITH
2469