

GOVERNMENT CORNER RESTORATION FORM

Date: 6/5/97 By: BC

This survey consists of:

Township 255 Range 5W Sec. 7 County DOUGLAS Map:

State OR Date 5-29-97 No.

Narrative:
Corner Rep: CS 6A/75-3

Corner Designation

1/4 S 7
S 15 18

DOUGLAS COUNTY
SURVEYOR

Condition Report Only

Not Found

Renewed

Unrecorded

Surveyed In

Referenced Out

MONUMENT DETAIL

Previous Renewals 1919 + 1960 OCSO

Monument(s) Found: (Condition and Source)

1/4" OLD IRON PIPE RUSTED
INTO TWO PIECES PARTIAL
ON TOP OF GROUND MEASUREMENTS
19" LONG. (1919)

N/A

Accessories Found:

24" NOW ROTTED NEARLY TO GROUND OAK WITH SCRIBING
VISIBLE "BT" BEARS N 45° W, 17.8 FT
(AGREES WITH REC.) OBT

11" NOW 23" DIA. D. FIR WITH A FULLY HEADED
DOUBLE BLADE BEARS S 26° E, 46.7 FT
(AGREES WITH REC.) 1960

20" NOW 26" DIA 1 1/2 FT OAK STUMP WITH
A HEADED BLADE BEARS N 36° W, 49.4 FT
(AGREES WITH REC.) 1960

Monument Set (Procedure and Description)

Monument Detail

PORTION OF FD IRON IN GROUND,
 MEASURES 24" LONG, A 2 3/8"
 DIA. BRASS CAP ON A 1 3/8" OD
 BY 32" LONG IRON PIPE IS
 SET AT POSITION OF FOUND
 IRON PIPE, PROTRUDS 6"
 ABOVE GROUND. PIECES OF FD
 IRON PIPE ARE SET ALONG
 NORTH EDGE OF BC/IP FLUSH
 WITH GROUND.

DOUGLAS COUNTY SURVEYORS

T25S
R5W


1/4 57
518

1997
OFFICE

New Accessories

11" DIA D. FIR DOUBLE BLAZED AND SCRIBED "Y457CSBT"
 BEARS N55°E, 24.1 FT
 24" DIA MADRONE DOUBLE BLAZED AND SCRIBED "Y457ZCSBT"
 BEARS N79°W 22.9 FT
 12" DIA D. FIR DOUBLE BLAZED AND SCRIBED "Y4518CSBT"
 BEARS S71°E, 16.3 FT

Sketch of Monument, Accessories, and General Area



Location & Comments

Comp. Declin. 173/4°E
 Agency DCSO
 Party Chief RANDALL W. SMITH
 Notekeeper [Signature]
 Witnesses STEPHEN J. FLAUS

Address

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

RANDALL W. SMITH
 EXPIRES 6-30-98

OREGON
 JULY 25, 1980
 RANDALL W. SMITH
 2469