

GOVERNMENT CORNER RESTORATION FORM

Date: 6/30/97 By: PRC

Township 25S Range 5W Sec. 9

County DOUGLAS Map: _____

This survey consists of: _____

State OR Date 6-26-97

No. _____

Narrative: _____

Corner Rpt: CS 64 75-17

Corner Designation

INT SW COR
DLC 58

PT#058040

DOUGLAS COUNTY
SURVEYOR

Condition: Renewed Only

Not Found

Renewed

Unrecorded

Surveyed In

Referenced Out

MONUMENT DETAIL

Previous Renewals 1919, 1950 + 1969 DCSO

Monument(s) Found: (Condition and Source)

1/2" I.D. IRON PIPE, PROTRUDS
3" ABOVE GROUND (1919)

3/4" I.D. I.P. THE SSW COR.
OF DLS 58 BEARS S 12 1/2° E
79.3 FT.

N/A

Accessories Found:

30" B. OAK NOW ROOT HOLE NEAR REC.
" N 4 3/4° E 30.7 FT " 1919

6" NOW 10" DIA. MADRONE WITH A FULLY HEALED DOUBLE
BLAZE, BEARS S 48° E, 7.8 FT (AGREES WITH REC.) 1950

5" NOW 20" DIA. D. FIR WITH A FULLY HEALED BLAZE
BEARS N 54 1/2° E, 15.5 FT (AGREES WITH REC.) 1969

RENEWAL

Monument Set (Procedure and Description)

Monument Detail

NONE


N/A

New Accessories

12" DIA D.F.I.R. DOUBLE BLAZED AND SCRIBED "INT SW DLC 58 CS BT"
BEARS S 29° W, 26.7 FT

9" DIA MADRONE DOUBLE BLAZED AND SCRIBED "INT SW DLC 58 CS BT"
BEARS N 16 1/2° W, 11.2 FT

Sketch of Monument, Accessories, and General Area



Location & Comments

Comp. Declin. 1734°E
 Agency DCSO
 Party Chief RANDALL W SMITH
 Notekeeper [Signature]
 Witnesses STEPHEN J FLAVEL

Address

Surveyor's Seal
 REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
 [Signature]
 CHAIRS 6-30-98
 OREGON
 JULY 25, 1990
 RANDALL W. SMITH
 2489