

GOVERNMENT CORNER RESTORATION FORM

Date: 2/12/98 By: X
This survey consists of:

Township 25S Range 6W Sec. 10
State OK Date 2-5-98

County DOUGLAS No. _____
Narrative: _____
Corner Rpt: 64/79-22

Corner Designation

$\frac{1}{4}$ $\frac{S10}{S15}$

- DOUGLAS COUNTY
 Condition: SURVEYED ONLY
 Not Found
 Renewed
 Unrecorded
 Surveyed In
 Referenced Out

Previous Renewals 1962 DCSO

Monument(s) Found: (Condition and Source)

2 1/2" DIA BRASS CAP IN A
1 1/2" OD IRON PIPE PROTRUDING
12" ABOVE GROUND, (1962)

COUNTY SURVEYORS OFFICE
T 25S
 $\frac{1}{4}$ $\frac{S10}{S15}$
R 6W
1962

Accessories Found:

- 18" NOW 24" DIA. 20 FT HIGH B. OAK SNAG
PREVIOUSLY OPENED AND ROTTED, NO SCRIBING
VISIBLE, BEARS S69°W, 27.1 FT (AGREES WITH
1962 REC.) OBT
- 15" NOW 20" DIA. 1 FT HIGH OAK STUMP,
A PREVIOUSLY OPENED AND ROTTED, NO SCRIBING VISIBLE
BEARS N22°W, 29.7 FT (AGREES WITH 1962 REC.) OBT
- 15" NOW 25" DIA D. FIR WITH A FULLY HEALED
DOUBLE BLAZE, BEARS S77°W, 15.3 FT (AGREES
WITH REC.) 1962
- 6" NOW 12" DIA. D. FIR WITH A FULLY HEALED
DOUBLE BLAZE, BEARS N23°E, 10.6 FT
(AGREES WITH REC.) 1962

Monument Set (Procedure and Description)

Monument Detail

NONE


N/A

New Accessories

9" DIA. D. FIR DOUBLE BLAZED AND SCRIBED "Y4S15CS BT"
BEARS S 12 1/2° W, 12.8 FT

18" DIA MADRONE DOUBLE BLAZED AND SCRIBED "Y4S15CS BT"
BEARS S 38 1/2° E, 25.5 FT

Sketch of Monument, Accessories, and General Area



Location & Comments

Comp. Declin. 17 1/4° E

Agency DCSO

Party Chief RANDALL W. SMITH

Notekeeper [Signature]

Witnesses STEPHEN J. FRAUSE

Address

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
EXPIRES 6-30-99

OREGON
JULY 25, 1990
RANDALL W. SMITH
2489