

FILED

Date: 9-28-95 By: JP

This survey consists of:

Map: _____

Narrative: _____

Corner Plat: CS 65/1-2

OREGON CORNER RESTORATION FORM

Section 14 Township 22S Range 4W

County Douglas Date 9/11/95

DOUGLAS COUNTY SURVEYOR

Corner Designation

Northwest Section Corner

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc.

Weyerhaeuser 1957, Weyerhaeuser 1963, D.C.S.O. 1965

Monument(s) & Accessories Found: (Condition and Source)


D.C.S.O. Brass Cap dated 1965 with 1957 Mmel pipe alongside

40" Fir Stump, S48E 44.6 ft to 'W' nail - scribing visible
Record: S48E, 44.6 ft. - 1963 Weyerhaeuser

20" Fir N24E 24.4 ft - closed face
Record: N23E, 23.5 ft. to 'W' nail - 1963 Weyerhaeuser

Monument Detail

Sketch



Monument Set (Procedures and Description)

None

New Accessories

13" Fir, S78E 6.2 ft. to 'W' nail - scribed "T22S R4W S14 BT"


11" Alder S44W 8.4 ft. to 'W' nail - scribed "T22S R4W S15 BT"

9" Fir N3E 13.1 ft. to 'W' nail scribed "T22S R4W S11 BT"

Location & Comments

Surveyor's Seal

Compass Declination 20°E
 Firm/Agency Baker & Assoc. Surveyors
 Address 1385 Oak St. Ste #3 Eugene OR 97401
 Party Chief Pat Irvin
 Notes _____
 Witness Spencer Noland



EXPIRES 12/31/75

C.S. File No. 65/1-2