

M 123-51

David A. Edwards - Professional Land Surveyor

P.O. Box 41
Oakland, OR 97462



(541) 459-0512

SURVEY NUMBER M123-51

SURVEY NARRATIVE TO COMPLY WITH CHAPTER 209, PARAGRAPH 250, OREGON REVISED STATUTES

SURVEY FOR: David Edwards Land Surveying
P.O. Box 41
148 Three Forks Lane
Oakland, Oregon 97462

LOCATION: In Section 7, T. 22 S., R. 6 W., W.M., in Douglas County, Oregon.

PURPOSE: To correct data shown on M122-72 which was performed by this office. The error caused the center 1/4 and CN 1/16 corners to be set incorrectly on M122-72. Both corners were reset in the positions shown on the attached map.

PROCEDURE: After discovery of the error, the subdivision of Section 7 was re-computed as shown. The same bearing trees which were scribed in M122-72 were used. Monuments set on this survey consist of 5/8" x 30" steel pins with red plastic caps mkd. "D.A. EDWARDS-LS 2339". The bearing trees are situated as follows:

At the CN 1/16 corner in Section 7:
An 11" diam. Fir brs. N. 20° E., 3.26 feet.
A 12" diam. Fir brs. N. 78°30' W., 2.94 feet.

The erroneous position of this corner per M122-72 bears N. 0° 33' 04" W., 3.53 feet.

At the Center 1/4 corner in Section 7:
A 14" diam. Fir brs. N.21°30'E., 13.13 feet.
A 7" diam. Cedar brs. S.18°30'E., 27.85 feet.
An 8" diam. Fir brs. S. 65° W., 21.03 feet.
A 9" diam. Fir brs. N. 19° W., 14.94 feet.

The erroneous position of this corner per M122-72 bears N. 0° 33' 04" W., 7.06 feet.


BASIS OF BEARINGS: 1855 G.L.O. Record as shown.

EQUIPMENT: Nikon DTM-A5 electronic total station.

DATE COMPLETED: April 4, 1996.

FILED

Date: 4/17/96 By: BC
This survey consists of:
Map: M123-51
Narrative: CS 105/5-6
Corner Rpt: _____



DOUGLAS COUNTY SURVEYOR

C S File 65, 5-6