

GOVERNMENT CORNER RESTORATION FORM

Date: 11-6-96 By: LP

This survey consists of:

Township 15 Range 7N Sec. 23 County DOUGLAS

Map: \_\_\_\_\_

State OR Date 11-6-96

Narrative: \_\_\_\_\_

No. \_\_\_\_\_ Corner Rpt: C.S. 65/9-10

Corner Designation

DOUGLAS COUNTY  
SURVEYOR

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

1/4 225/524

MONUMENT DETAIL

Previous Renewals 1966 DCSC

Monument(s) Found; (Condition and Source)

16" NOW 27" DIA 7' HIGH PINE STUMP WE CAN FIND HIGHER THAN 1966 DCSC RENEWAL, NO SCRIBING FOUND. (CRIG. CORNER TREE)

2 1/2" DIA. BRASS CAP ON A 1 1/2" O.D. IRON PIPE PROTRUDING 18" ABOVE GROUND. FOUND ALONG WEST EDGE OF CRIG CORNER TREE. (1966 DCSC)

CENTER OF CORNER TREE BEARS EAST 1 FT

Accessories Found:

(BRG + DIST FROM CORNER TREE)  
12" NOW 16" DIA CEDAR WITH AN UNRECORDED BLAZE, SCRIBING VISIBLE "1/4 S" BEARS N 27° W, 23.1 FT (1966 REC N 27° W 22.4 FT POSSIBLE FACE MEASUREMENT) 1 FT

34" NOW 46" DIA. 8 FT HIGH CEDAR STUMP NO BLAZE VISIBLE, BEARS N 7 1/2° E, 30.4 FT AGREES WITH 1966 REC.)  
OBT

(BRG + DIST FROM BC/IP TO OBT'S)

16" DIA. CEDAR N 26 1/2° W, 23.1 FT

46" DIA CEDAR STUMP N 73° E, 30.9 FT

COUNTY SURVEYORS OFFICE

T 315

1/4 225/524

1966

RENEWAL

Monument Set (Procedure and Description)

Monument Detail

N/A

N/A

(BRG + DIST TAKEN FROM BC/IP)

New Accessories

7" DIA D. FIR DOUBLE BLAZED AND SCRIBED "4524CS BT"  
BEARS N 11 1/2° E, 10.9 FT.


8" DIA. PISTOL BUTT D. FIR DOUBLE BLAZED AND SCRIBED "4523CS BT"  
BEARS N 79° W, 11.7 FT TO CENTER OF TRUNK

7" DIA. D. FIR DOUBLE BLAZED AND SCRIBED "4524CS BT"  
BEARS S 17° E, 29.5 FT

Sketch of Monument, Accessories, and General Area

Location & Comments

Location & Comments



Comp. Declin. 17 3/4° E  
 Agency DCSO  
 Party Chief RANDALL W. SMITH  
 Notekeeper [Signature]  
 Witnesses [Signature]

Address

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

[Signature]  
 EXPIRES 6-30-98

OREGON  
 JULY 25, 1990  
 RANDALL W. SMITH  
 2469