

AFFIDAVIT OF CORRECTION - SURVEY

I, Daniel W. Baker, being duly sworn, depose and say that I am the Surveyor who surveyed the property as depicted, filed, and recorded in C.S. M118-43, Douglas County, Oregon Survey Records; and


The following corrections to said plat are necessary and are as follows:

The Center 1/4 corner monument was found to have been set from the wrong transit hub. The corrected corner position was monumented on August 7, 1997 by this Company. The erroneous corner monument was removed and associated bearing trees chopped out. The brass cap as noted on the plat remains the same. All shown plat calls to the monument position are correct, and remain the same. Monument size and bearing trees have changed. The correct corner and information is as follows:

- Set: 1-1/2" x 36" Iron Pipe with 2-1/2" brass cap dated 1997
- 9" Fir, N 73° E, 9.9 Ft. to "W" nail
- 10" Fir, S 61 E, 17.1 Ft. to "W" nail
- 9" Fir, S 31 E, 18.9 Ft. to "W" nail
- 9" Fir, S 21 W, 2.4 Ft. to "W" nail

All bearings to bearing trees are magnetic 20° Declination and scribed "C 1/4 S7".

[Signature]
 Daniel W. Baker
 Registered Professional Land Surveyor - PLS #1978
 Baker & Associates, Surveyors Inc.
 1385 Oak Street, Ste. #3
 Eugene, OR 97401



Expires 12/31/97
 FILED
 (Stamp/Seal)

Date: 8-21-97 By: JP
 This survey consists of:
 For Map: M118-43
 Narrative: CS 65/14-9
 Corner Rpt: _____

NOTARY CERTIFICATE


State of Oregon)
)ss
 County of Lane)

STATE OF OREGON)
 COUNTY OF DOUGLAS) SS
 I, DOYLE SHAVER JR., COUNTY CLERK AND
 RECORDER OF CONVEYANCES, DO HEREBY CERTIFY
 THAT THIS INSTRUMENT WAS RECORDED

97 AUG 19 AM 8:05

Subscribed and sworn to me this 14 day of August, 1997
 IN THE OFFICIAL RECORDS OF DOUGLAS COUNTY

[Signature] BY *[Signature]*
 Notary Public for Oregon DEPUTY
 My Commission Expires 1/23/01
 FEE 5.10



(Stamp/Seal)

COUNTY SURVEYOR APPROVAL

I, Roman E. White, Douglas County Surveyor, do hereby certify that said affidavit of Correction for C.S. M118-43 has been examined by me and that it complies with ORS 209.255.

[Signature] 8-18-97
 Roman E. White

Douglas County Surveyor

Surveyor ✓